



## City of Phoenix

PLANNING & DEVELOPMENT DEPARTMENT

**To:** Departments Concerned  
**From:** Joshua Bednarek  
Planning & Development Department Director  
**Date:** June 13, 2024

**Subject: P.H.O. APPLICATION NO. PHO-1-24--Z-104-23-8** – Notice of Pending Actions by the **Planning Hearing Officer**

1. Your attention is called to the fact that the **Planning Hearing Officer** will consider the following case at a public hearing on **July 17, 2024**.
2. Information about this case is available for review at the Zoning Counter in the Planning and Development Department on the 2nd Floor of Phoenix City Hall, telephone 602-262-7131, Option 6.
3. Staff, please indicate your comments and respond electronically to [pdd.pho@phoenix.gov](mailto:pdd.pho@phoenix.gov) or you may provide hard copies at the Zoning Counter in the Planning and Development Department on the second floor of Phoenix City Hall by **June 20, 2024**.

### **DISTRIBUTION**

Mayor's Office (Tony Montola), 11th Floor  
City Council (Stephanie Bracken), 11th Floor  
Aviation (Jordan D. Feld )  
CED (Michelle Pierson), 20th Floor  
Fire Prevention (Joel Asirsan), 2nd Floor  
Neighborhood Services (Gregory Gonzales, Lisa Huggins), 4th Floor  
Parks & Recreation (Todd Shackelford), 16th Floor  
Public Transit (Michael Pierce)  
Street Transportation Department (Maja Brkovic, Josh Rogers, Alan Hilty, Chris Kowalsky), 5th Floor  
Street Transportation - Ped. Safety Coordinator (Kurt Miyamoto), 5th Floor  
Street Transportation - Floodplain Management (Tina Jensen, Priscilla Motola, Rudy Rangel), 5th Floor  
Water Services (Don Reynolds, Victor Romo), 8th Floor  
Planning and Development (Joshua Bednarek, Tricia Gomes), 3rd Floor  
Planning and Development/Information Services (Ben Ernyei, Andrew Wickhorst), 4th Floor  
Planning and Development/Historic Preservation Office (Kevin Weight), 3rd Floor  
Planning Hearing Officer (Byron Easton, Teresa Garcia), 2nd Floor  
Village Planner (Samuel Rogers, South Mountain Village)  
Village Planning Committee Chair (Trent Marchuk, South Mountain Village)



# City of Phoenix

PLANNING & DEVELOPMENT DEPARTMENT

## APPLICATION FOR PLANNING HEARING OFFICER ACTION

APPLICATION NO: PHO-1-24--Z-104-23-8

Council District: 8

**Request For:** Stipulation Modification

**Reason for Request:** Modification to Stipulation 34 regarding conceptional elevation review.

### Contact Information

Name	Relationship Type	Address	Phone	Fax	Email
Ryan Larsen-Porchlight Homes	Applicant	2915 East Baseline Road, Suite 118, Gilbert AZ 85234	602-206-6211		rlarsen@porchlighthomes.com
Yvonne and Miguel Montiel; All Other Property, LLC.	Owner	809 North Ridgeview Drive, Phoenix AZ 85253			
Ryan Larsen-Porchlight Homes	Representative	2519 East Baseline Road, Suite 118, Gilbert AZ 85234			

**Property Location:** Northeast corner of 36th Street and Beverly Road

**Acreage:** 18.52

### Geographic Information

Zoning Map	APN	Quarter Section
D10	301-20-007C	Q01-36
D10	301-20-010J	Q01-36
D10	301-20-010G	Q01-36
D10	301-20-049B	Q01-36
D10	301-20-050	Q01-36
D10	301-20-221	Q01-36
D10	301-20-222	Q01-36
D10	301-20-223	Q01-36
D10	301-23-004C	Q01-35
D10	301-23-003F	Q01-36
D10	301-20-001	Q01-36

Village:  
South Mountain

An applicant may receive a clarification from the city of its interpretation or application of a statute, ordinance, code or authorized substantive policy statement. To request clarification or to obtain further information on the application process and applicable review time frames, please call 602-262-7131 (option 6), email [zoning@phoenix.gov](mailto:zoning@phoenix.gov) or visit our website at <https://www.phoenix.gov/pdd/licensing-time-frames>

A Filing Fee had been paid to the City Treasurer to cover the cost of processing this application. The fee will be retained to cover the cost whether or not the request is granted

I declare that all information submitted is true and correct to the best of my knowledge and belief. I acknowledge that any error in my application may be cause for changing its normal scheduling.

Signature: \_\_\_\_\_ DATE: \_\_\_\_\_

**Fee Information**

Fee	Fee Waived	Fee Date	Purpose
\$1,080.00	\$0.00	05/31/24	PHO (1-2 stipulations)



# PORCHLIGHT H O M E S

2915 E Baseline Road, Suite 118  
Gilbert, Arizona 85234  
Office - (480) 813-1324  
lpowell@porchlighthomes.com

May 30, 2024

Byron Easton  
Planning Hearing Officer  
Phoenix Planning & Development Department  
200 West Washington Street, 2<sup>nd</sup> Floor  
Phoenix, Arizona 85003

Re: PHO Elevation Review - Case No. Z-104-23-8 – Northeast corner of 36<sup>th</sup> Street and Beverly Road, Phoenix

Dear Mr. Easton:

Porchlight Homes, the “Applicant” is submitting this request for a housing development located at the northeast corner of 36<sup>th</sup> Street and Beverly Road in Phoenix. The subject site is approximately 18 gross acres and comprises APNs 301-20-001, 301-20-007C, 301-20-010G, 301-20-010J, 301-20-049Bm 301-20-050, 301-20-221, 301-20-222, 301-20-223, 301-23-004C, and 301-23-003F (the “Property”). See aerial map at **Tab 1**.

More specifically, the PHO request is the review of elevations, as required by one of their stipulations associated with zoning case no. Z-104-23-8 that rezoned the site to R1-6 BAOD (Single-family Residence District, Baseline Area Overlay District) to allow a single-family subdivision. This zoning case was approved by the Phoenix City Council on April 3, 2024 per Ordinance G-7243, a copy of which is attached at **Tab 2**.

## PROPOSAL

The conceptual site plan provided identifies 61 single-family residential lots. See Conceptual Site Plan, **Tab 3**. The Property is accessed via 36<sup>th</sup> Street. Emergency access is provided on the north side of the Property via a public street stub in the existing subdivision. Approximately 3.9 acres of the Property is devoted to common area open space, which is nearly five times the amount required in the R1-6 District. Open space areas with turf are provided throughout the community and a centrally located ramada and play structure are provided to foster community engagement. Each residence will include a two-car garage and provided parking complies with Section 702 of the Phoenix Zoning Ordinance.

In addition, the Applicant is proposing a set of elevations for their single-family homes that are in line with the Baseline Area Overlay District and Single-Family Design Review Guidelines, as detailed below. See Elevations, **Tab 4**.

Porchlight Homes has prepared this submittal in accordance with the Single-Family Residential Housing Design Review Development Guidelines and will demonstrate how this project can meet the Standard Approach or Alternative Approach requirements. Herewith please find a narrative justification when the Alternative Approach is selected and demonstration of compliance for the Standard Approach. Please note that the house width for this project is 45' so requirements for > 40' to 50' shall apply.

The elevations include the following elements:

I. SUBDIVISION DESIGN (Alternative Approach)

(1) Vary building's relationship to the street.

(a) The curvilinear shape of the Highline Canal creates asymmetry in the lot layout and allows for no more than 9 contiguous lots in a row. The presence of a 30'+ hill in the center of the community also creates a visually appealing and unstructured feel to the subdivision breaking up the potential monotony of rows of unvaried lots. All homes will be setback 20' from the street and min of 26' to front a garage face. All plans have been designed with an articulated front façade to create an appealing street scene and a varied building relationship with the street. Each home will have a forward-facing garage that is set back a minimum of 8' from the front façade or porch of the home to create an enhanced staggering effect across the project. Creating a 5ft stagger for one lot in each block would adversely impact the house plan.

(b) Streets will be provided as per the Preliminary Site Plan

(2) Vary the driveway orientation or location for 25% of the lots in each subdivision.

(d) Pavers will be offered as an alternative driveway surface in lieu of concrete driveways.

(3) Vary the relationship between buildings.

(g) Relationships between buildings will be varied by providing a combined side yard of 10 feet for all lots on each block face, per the submitted Plot Plans.

(4) Vary street orientation.

(i) Street orientation is designed as short length that minimizes the impact of sequential garages, per the Preliminary Site Plan.

II. HOUSING DESIGN (Standard Approach)

(a) Three (3) different elevation designs will be provided for each plan; this will yield nine (9) distinctive elevations designs provided within the community. They include Santa Barbara Contemporary, Modern Desert Prairie and Mid-Century Modern.

(b) Nine (9) distinct color schemes will be provided which include three schemes per elevation.

(c) Three (3) distinctive roof tiles colors will be provided as per the color scheme exhibits provided within this submittal.

(d) Exterior accent materials consisting of thin brick, cultured stone and contemporary ledge stone provided as standard materials per elevation.

(e) A sand finish stucco texture will be offered within the community. No additional texture is required.

(f) Front yard landscaping will be provided with 2-24" box trees 25' apart to provide shade to the sidewalk per the Baseline Area Overlay District

- (g) Three standard plans will be offered with each having three elevations to choose from.
- (h) Each standard plan will have three distinctive elevations that offer specific exterior detailing.
  - Santa Barbara Contemporary – this elevation will include several arched windows, window overhang affixed with metal rods for a contemporary look, modern front door with a pop of color, sand stucco finish and a “S” profile rood tile.
  - Modern Desert Prairie – this elevation will include low pitched hip roofs, extended eaves, contemporary ledgestone, modern window overhangs, decorative pop outs, covered front porches and a low-profile flat roof tile with straight edge.
  - Mid-Century Modern – this elevation will include angled and flat rooflines, stone veneer, modern color blocking and a low-profile flat roof tile with tapered edge.

### III. GARAGE TREATMENT (Standard Approach)

- (a) The house width will be forty-five feet (45') and each home will have a forward-facing standard two car garage door measuring sixteen feet (16'). In addition, 10% of the community will have a side entry garage per the Baseline Area Overlay requirements.
- (b) All plans have the garage positioned eight feet (8') or less behind the front plane of a covered porch with the exception of our side entry garage required by the Baseline Area Overlay.
- (d) Three (3) distinctive garage door designs with raised and flat panels and windows will be provided as per the standard plan elevations.
- (e) Plan 3 includes a 3-car garage however the third is a side entry garage required by the Baseline Area Overlay requirements.
- (f) Requirement met. Only one plan has a three-car garage and it is a side entry garage per the Baseline Area Overlay requirement.

### IV.COMMUNITY SAFETY (Standard Approach)

- (a) All elevations shall provide front entrances which are visible from the street or adjacent open space.
- (b) Architectural features such as a front porch and street facing front door clearly delineates the front entry of the home.

### PHO ELEVATION REVIEW

To allow the proposed redevelopment of the Property, the Owner requests the PHO Elevation Review by the Planning Hearing Officer process, including review by the South Mountain Village Planning Committee, as noted in stipulation #34 per Z-104-23-8, which notes:

*34. The conceptual elevations for future development (new homes) shall be reviewed and approved, with specific regard to the Single-Family Design Review Guidelines, by the Planning Hearing Officer through the public hearing process, including review by the South Mountain Village Planning Committee, for stipulation modification prior to preliminary site plan approval. This is a legislative review for conceptual purposes only.*

*Specific development standards and requirements will be determined by the Planning Hearing Officer, and the Planning and Development Department.*

Therefore, we are requesting this application to satisfy this stipulation above, and to continue development of the single-family residential subdivision.

**CONCLUSION**

In order to continue with the development of this subdivision, the elevation review via the PHO process is required. We look forward to presenting the proposed elevations for review.

Very truly yours,


Porchlight Homes

Attachments

TAB 1



# Aerial Map



Baseline Rd

S/SEC Baseline Rd and 36<sup>th</sup> St, Phoenix



Tab 2

ORDINANCE G-7243

AN ORDINANCE AMENDING THE ZONING DISTRICT MAP ADOPTED PURSUANT TO SECTION 601 OF THE CITY OF PHOENIX ZONING ORDINANCE BY CHANGING THE ZONING DISTRICT CLASSIFICATION FOR THE PARCEL DESCRIBED HEREIN (Z-104-23-8) FROM R1-6 BAOD (APPROVED R1-10 BAOD) (SINGLE-FAMILY RESIDENCE DISTRICT, BASELINE AREA OVERLAY DISTRICT, APPROVED SINGLE-FAMILY RESIDENCE DISTRICT, BASELINE AREA OVERLAY DISTRICT), S-1 BAOD (APPROVED R1-10 BAOD) (RANCH OR FARM RESIDENCE, BASELINE AREA OVERLAY DISTRICT, APPROVED SINGLE-FAMILY RESIDENCE DISTRICT, BASELINE AREA OVERLAY DISTRICT), AND S-1 BAOD (RANCH OR FARM RESIDENCE, BASELINE AREA OVERLAY DISTRICT) TO R1-6 BAOD (SINGLE-FAMILY RESIDENCE DISTRICT, BASELINE AREA OVERLAY DISTRICT).

---

BE IT ORDAINED BY THE COUNCIL OF THE CITY OF PHOENIX, as follows:

SECTION 1. The zoning of an 18.52-acre site located at the northeast corner of 36th Street and Beverly Road in a portion of Section 1, Township 1 South, Range 3 East, as described more specifically in Exhibit "A," is hereby changed from 0.83 acres of "R1-6 BAOD (Approved R1-10 BAOD)" (Single-Family Residence District, Baseline Area Overlay District, Approved Single-Family Residence District, Baseline Area Overlay District), 6.74 acres of "S-1 BAOD (Approved R1-10 BAOD)" (Ranch or

Farm Residence, Baseline Area Overlay District, Approved Single-Family Residence District, Baseline Area Overlay District), and 10.95 acres of "S-1 BAOD" (Ranch or Farm Residence, Baseline Area Overlay District) to "R1-6 BAOD" (Single-Family Residence District, Baseline Area Overlay District).

SECTION 2. The Planning and Development Director is instructed to modify the Zoning Map of the City of Phoenix to reflect this use district classification change as shown in Exhibit "B."

SECTION 3. Due to the site's specific physical conditions and the use district applied for by the applicant, this rezoning is subject to the following stipulations, violation of which shall be treated in the same manner as a violation of the City of Phoenix Zoning Ordinance:

1. Tracts "C", "H", "I", and "G", as generally depicted on the site plan date stamped January 17, 2024, shall be reserved for open space, as modified by the following stipulations, and approved by the Planning and Development Department.
2. The undisturbed hillside area (above 10% per the approved Slope Analysis) shall remain undisturbed and be dedicated with a preservation easement except for Lot 27 and development of private accessways as generally depicted on the site plan date stamped January 17, 2024, as approved by the Planning and Development Department.
3. The existing home on Lot 27 shall remain and any improvements to this lot shall be reviewed and approved through a Hillside/Grading and Drainage Plan by the Planning and Development Department.
4. A physical feature (such as retaining wall, rock wall, etc.) shall be provided along the west and south portions of Tract "J", as generally depicted on the site plan date stamped January 17, 2024, to protect the undisturbed hillside area, as approved by the Planning and Development Department.

5. A minimum of three distinct exterior accent materials for each required standard plan within the subdivision shall be provided, as approved by the Planning and Development Department.
6. If fencing is proposed along the perimeter of the site, the fencing shall be a minimum of 75% view fencing, except on Lots 1, 50, 51, 52, and 53 as depicted on the site plan date stamped January 17, 2024, as approved by the Planning and Development Department. Any perimeter fencing requirement adjacent to the Highline Canal is subject to review and approval of SRP.
7. All landscape setbacks shall be planted with minimum 2-inch caliper large canopy drought-tolerant trees, 20 feet on center or in equivalent groupings, with five 5-gallon shrubs per tree, as approved by the Planning and Development Department.
8. A minimum of 10% of the required shrubs, shall be a milkweed or other native nectar species, and shall be planted in groups of three or more and maintained, as approved by the Planning and Development Department.
9. The sidewalk along 36th Street shall be a minimum of five feet in width and detached with a minimum five-foot wide landscape strip located between the sidewalk and back of curb and planted to the following standards, as approved by the Planning and Development Department.
  - a. Minimum 2-inch caliper, single-trunk, large canopy, drought-tolerant shade trees planted 20 feet on center or in equivalent groupings.
  - b. Drought tolerant vegetation to achieve a minimum of 75 percent live coverage at maturity.

Where utility conflicts exist, the developer shall work with the Planning and Development Department on alternative design solutions consistent with a pedestrian environment for installing the required plants.

10. Prior to preliminary plat approval, documentation shall be provided that demonstrates participation in the Environmental Protection Agency's WaterSense certification program, or an equivalent program, as approved by the Planning and Development and Water Services departments.

11. A WaterSense inspection report from a third-party verifier shall be submitted that demonstrates successful participation in the Environmental Protection Agency's WaterSense certification program, or an equivalent program, prior to certificate of occupancy, as approved by the Planning and Development Department.
12. In addition to the landscape materials listed in the Baseline Area Master Plan Plant List Cercidium Hybrid (Desert Museum Palo Verde), Quercus Virginiana (Live Oak), And Pistacia X 'Red-Push (Red Push Pistache), may be permitted as approved by Planning and Development Department and shall be utilized throughout the subdivision including the front, side, and rear yards of individual residential lots. This restriction shall be included in the Covenants, Conditions, and Restrictions for the subdivision.
13. Landscaping in common areas shall be maintained by permanent and automatic/water efficient WaterSense labeled irrigation controllers (Smart Controller) to minimize maintenance and irrigation water consumption for all on and offsite landscape irrigation.
14. Pressure regulating sprinkler heads and drip lines shall be utilized in any turf areas to reduce water waste.
15. Natural turf shall only be utilized on individual single-family lots (behind the front yard); required retention areas (bottom of basin), and functional turf areas within common areas, as approved by the Planning and Development Department.
16. A minimum of two green infrastructure (GI) techniques for stormwater management shall be implemented per the Greater Phoenix Metro Green Infrastructure and Low-Impact Development Details for Alternative Stormwater Management, as approved or modified by the Planning and Development Department.
17. Swimming pools on individual single-family lots shall be limited to 600 square feet in size.
18. A public connection to the existing 36th Way stub street shall be provided or the existing 36th Way right-of-way shall be terminated per the City of Phoenix termination standards, as required by the Street Transportation Department.

19. An enhanced connection shall be provided on the southern site boundary to allow for direct pedestrian access to the adjacent Highline Canal. The developer shall construct an 8-foot-wide shaded pedestrian pathway consisting of decorative material such as brick, pavers or alternative material providing at the entryway, as approved by the Planning and Development Department.
20. A sidewalk easement shall be dedicated over a clearly defined pedestrian pathway(s) providing a public connection through the site from the existing 36th Way access point on the northern site boundary to the Highline Canal and the adjacent wash/trail system, as approved by the Planning and Development Department.
21. Replace unused driveways with sidewalk, curb, and gutter. Also, replace any broken or out-of-grade curb, gutter, sidewalk, curb ramps on all streets and upgrade all off-site improvements to be in compliance with current ADA guidelines.
22. All streets within and adjacent to the development shall be constructed with paving, curb, gutter, sidewalk, curb ramps, streetlights, median islands, landscaping and other incidentals, as per plans approved by the Planning and Development Department. All improvements shall comply with all ADA accessibility standards
23. The property owner shall record documents that disclose the existence, and operational characteristics of Phoenix Sky Harbor Airport to future owners or tenants of the property. The form and content of such documents shall be according to the templates and instructions provided which have been reviewed and approved by the City Attorney.
24. If determined necessary by the Phoenix Archaeology Office, the applicant shall conduct Phase I data testing and submit an archaeological survey report of the development area for review and approval by the City Archaeologist prior to clearing and grubbing, landscape salvage, and/or grading approval.
25. If Phase I data testing is required, and if, upon review of the results from the Phase I data testing, the City Archaeologist, in consultation with a qualified archaeologist, determines such data recovery excavations are necessary, the applicant shall conduct Phase II archaeological data recovery excavations.


26. In the event archaeological materials are encountered during construction, the developer shall immediately cease all ground-disturbing activities within a 33-foot radius of the discovery, notify the City Archaeologist, and allow time for the Archaeology Office to properly assess the materials.
27. Prior to final site plan approval, the landowner shall execute a Proposition 207 waiver of claims form. The waiver shall be recorded with the Maricopa County Recorder's Office and delivered to the City to be included in the rezoning application file for record.
28. Bench seating shall be provided near the western pedestrian connection, located between Lots 39 and 50, as depicted on the site plan date stamped January 17, 2024, and as approved by the Planning and Development Department.
29. At least 50% of the residential homes abutting the canal (Lots 28 through 39, as depicted on the site plan date stamped January 17, 2024) shall be a maximum of one story or 15 feet in height, as approved by the Planning and Development Department.
30. The developer shall provide evidence of undertaking reasonable efforts to work with the adjacent homeowners association to the north, to close off the former access drive east of the "Groves at Baseline" subdivision by installing a solid 4-foot tall block wall with a 2-foot view fence atop, at the northeast corner of the site and at the driveway entrance along Baseline Road, with a locked access gate on the south end for maintenance as needed.
31. A Traffic Impact Analysis (TIA) shall be submitted to the City for this development. No preliminary approval of plans shall be granted until the analysis is reviewed and approved by the Street Transportation Department. The TIA shall include a signal warrant analysis for 36th Street and Baseline Road. If the approved TIA determines that a signal is warranted and is approved by the Street Transportation Department for installation, the developer shall be responsible for its proportionate share of the funding and construction of all recommendations of the analysis.
32. The subdivision shall have no more than 61 lots.



- 33. On-site lighting within open space areas shall be accomplished with low level, uniform light fixtures dispersed throughout the site with a lumen rating of 3,000 or less.
- 34. The conceptual elevations for future development (new homes) shall be reviewed and approved, with specific regard to the Single-Family Design Review Guidelines, by the Planning Hearing Officer through the public hearing process, including review by the South Mountain Village Planning Committee, for stipulation modification prior to preliminary site plan approval. This is a legislative review for conceptual purposes only. Specific development standards and requirements will be determined by the Planning Hearing Officer, and the Planning and Development Department.
- 35. Any invasive plants shall not be allowed.
- 36. Native materials, or similar materials, shall be used for all exterior perimeter wall columns, as approved by the Planning and Development Department.

SECTION 4. If any section, subsection, sentence, clause, phrase or portion of this ordinance is for any reason held to be invalid or unconstitutional by the decision of any court of competent jurisdiction, such decision shall not affect the validity of the remaining portions hereof.

PASSED by the Council of the City of Phoenix this 3rd day of April, 2024.


  
\_\_\_\_\_  
MAYOR  
4/5/2024  
\_\_\_\_\_  
Date

ATTEST:

  
\_\_\_\_\_  
Denise Archibald, City Clerk



APPROVED AS TO FORM:  
Julie M. Kriegh, City Attorney

By: 

\_\_\_\_\_ P ml

REVIEWED BY:

  
\_\_\_\_\_  
Jeffrey Barton, City Manager

PML:ac:(LF24-0553):4-3-24:2427108\_1.doc

Exhibits:

- A – Legal Description (2 Pages)
- B – Ordinance Location Map (1 Page)

**EXHIBIT A**

LEGAL DESCRIPTION FOR Z-104-23-8

A portion of the North half of Section 1, Township 1 South, Range 3 East of the Gila and Salt River Base and Meridian, Maricopa County, Arizona, more particularly described as follows:

Commencing at the North quarter corner of said Section 1;

Thence along the West line of the Northeast quarter of said Section 1, South 00 degrees 31 minutes 29 seconds West a distance of 835.13 feet to the beginning of a non-tangent curve whose center bears North 89 degrees 28 minutes 44 seconds West a distance of 500.00 feet;

Thence along the arc of said non-tangent curve through a central angle of 16 degrees 47 minutes 26 seconds and an arc length of 146.52 feet to the POINT OF BEGINNING;

Thence South 72 degrees 41 minutes 18 seconds East a distance of 30.00 feet to a point on the Easterly right of way line of 36th Street;

Thence North 89 degrees 40 minutes 26 seconds East a distance of 527.92 feet;

Thence North 00 degrees 34 minutes 55 seconds East a distance of 332.04 feet;

Thence North 89 degrees 51 minutes 09 seconds East a distance of 464.64 feet to a point on the West property line of Blossom Hills, a subdivision, as recorded in Book 899 of Maps, Page 7, records of Maricopa County, Arizona;

Thence along said West line, South 00 degrees 31 minutes 34 seconds West a distance of 666.62 feet;

Thence North 89 degrees 58 minutes 24 seconds East a distance of 129.98 feet to a point on the arc of a non-tangent curve whose center bears South 61 degrees 57 minutes 55 seconds East a distance of 323.00 feet, also being a point on the Northerly right of way line of the Highline Canal, as recorded in Book 122 of Deeds, Pages 1 through 9, records of Maricopa County, Arizona;

This along said right of way line the following 6 courses:

Thence along the arc of said non-tangent curve through a central angle of 7 degrees 35 minutes 20 seconds and an arc length of 42.78 feet;

Thence South 20 degrees 26 minutes 45 seconds West a distance of 120.01 feet to the beginning of a tangent curve whose center bears North 69 degrees 33 minutes 15 seconds West a distance of 187.90 feet;

Thence along the arc of said tangent curve through a central angle of 58 degrees 34 minutes 01 seconds and an arc length of 192.07 feet;

Thence South 79 degrees 00 minutes 46 seconds West a distance of 366.74 feet to the beginning of a tangent curve whose center bears North 10 degrees 59 minutes 14 seconds West a distance of 158.18 feet;

Thence along the arc of said tangent curve through a central angle of 56 degrees 46 minutes 19 seconds and an arc length of 156.73 feet; Thence North 44 degrees 12 minutes 55 seconds West a distance of 176.41 feet to the beginning of a tangent curve whose center bears South 45 degrees 47 minutes 05 seconds West a distance of 228.18 feet;

Thence along the arc of said tangent curve through a central angle of 50 degrees 23 minutes 19 seconds and an arc length of 200.67 feet;

Thence South 85 degrees 23 minutes 46 seconds West a distance of 123.36 feet;

Thence South 89 degrees 19 minutes 11 seconds West a distance of 70.30 feet;

Thence North 00 degrees 28 minutes 46 seconds East a distance of 144.59 feet to the beginning of a tangent curve whose center bears North 89 degrees 31 minutes 14 seconds West a distance of 117.87 feet;

Thence along the arc of said tangent curve through a central angle of 46 degrees 01 minutes 50 seconds and an arc length of 114.78 feet;

Thence North 45 degrees 31 minutes 27 seconds West a distance of 47.96 feet to a point on the arc of a non-tangent curve whose center bears North 45 degrees 26 minutes 34 seconds West a distance of 500.00 feet;

Thence along the arc of said non-tangent curve through a central angle of 27 degrees 14 minutes 28 seconds and an arc length of 237.80 feet to the POINT OF BEGINNING.



Note: The above described parcel contains 784,908 square feet or 18.0190 acres, more or less.

**G7243**

# ORDINANCE LOCATION MAP

Zoning Case Number: Z-104-23-8  
 Zoning Overlay: Baseline Area Plan and Overlay District  
 Planning Village: South Mountain

ZONING SUBJECT TO STIPULATIONS: \*  
 SUBJECT AREA: - - - - -



Tab 3

**NOTES**

- A. DEVELOPMENT AND USE OF THIS SITE WILL CONFORM TO ALL APPLICABLE CODES AND ORDINANCES.
- B. ALL NEW OR RELOCATED UTILITIES WILL BE PLACED UNDERGROUND
- C. ANY LIGHTING WILL BE PLACED SO AS TO DIRECT LIGHT AWAY FROM ADJACENT RESIDENTIAL DISTRICTS AND WILL NOT EXCEED ONE FOOT CANDLE AT THE PROPERTY LINE. NO NOISE, ODOR OR VIBRATION WILL BE EMITTED SO THAT IT EXCEEDS THE GENERAL LEVEL OF NOISE, ODOR, OR VIBRATION EMITTED BY USES OUTSIDE OF THE SITE.
- D. OWNERS OF PROPERTY ADJACENT TO PUBLIC RIGHT-OF-WAY WILL HAVE THE RESPONSIBILITY FOR MAINTAINING ALL LANDSCAPING WITHIN THE RIGHTS OF WAY, IN ACCORDANCE WITH APPROVED PLANS.
- E. ALL ROOFTOP EQUIPMENT AND SATELLITE DISHES SHALL BE SCREENED TO THE HEIGHT OF THE TALLEST EQUIPMENT.
- F. THIS PROJECT IS LOCATED IN THE CITY OF PHOENIX WATER SERVICE AREA AND HAS BEEN DESIGNATED AS HAVING AN ASSURED WATER SUPPLY.

I CONSENT TO THE REPRODUCTION OF THIS SITE PLAN PROVIDED THAT IF MODIFICATIONS ARE MADE, THE PROFESSIONALS WHO MAKE SUCH CHANGES ASSUME FULL RESPONSIBILITY AND LIABILITY FOR THE MODIFIED PORTIONS OF THE PLAN.

PRESIDENT	1-10-24
SIGNATURE OF COPYRIGHT OWNER	DATE
CLOUSE ENGINEERING, INC.	1-10-24
PRINT NAME OF COPYRIGHT OWNER	DATE

**LEGAL DESCRIPTION**

A PORTION OF THE NORTH HALF OF SECTION 1, TOWNSHIP 2 SOUTH, RANGE 3 EAST OF THE GILA AND SALT RIVER BASE AND MERIDIAN, MARICOPA COUNTY, ARIZONA, MORE PARTICULARLY DESCRIBED AS FOLLOWS:

COMMENCING AT THE NORTH QUARTER CORNER OF SAID SECTION 1;

THENCE ALONG THE WEST LINE OF THE NORTHEAST QUARTER OF SAID SECTION 1, SOUTH 00 DEGREES 31 MINUTES 29 SECONDS WEST A DISTANCE OF 835.13 FEET TO THE BEGINNING OF A NON-TANGENT CURVE WHOSE CENTER BEARS NORTH 89 DEGREES 28 MINUTES 44 SECONDS WEST A DISTANCE OF 500.00 FEET;

THENCE ALONG THE ARC OF SAID NON-TANGENT CURVE THROUGH A CENTRAL ANGLE OF 16 DEGREES 47 MINUTES 26 SECONDS AND AN ARC LENGTH OF 146.52 FEET TO THE POINT OF BEGINNING;

THENCE SOUTH 72 DEGREES 41 MINUTES 18 SECONDS EAST A DISTANCE OF 30.00 FEET TO A POINT ON THE EASTERLY RIGHT OF WAY LINE OF 36TH STREET;

THENCE NORTH 89 DEGREES 40 MINUTES 26 SECONDS EAST A DISTANCE OF 527.92 FEET;

THENCE NORTH 00 DEGREES 34 MINUTES 55 SECONDS EAST A DISTANCE OF 332.04 FEET;

THENCE NORTH 89 DEGREES 51 MINUTES 09 SECONDS EAST A DISTANCE OF 464.64 FEET TO A POINT ON THE WEST PROPERTY LINE OF BLOSSOM HILLS, A SUBDIVISION, AS RECORDED IN BOOK 899 OF MAPS, PAGE 7, RECORDS OF MARICOPA COUNTY, ARIZONA;

THENCE ALONG SAID WEST LINE, SOUTH 00 DEGREES 31 MINUTES 34 SECONDS WEST A DISTANCE OF 666.62 FEET;

THENCE NORTH 89 DEGREES 58 MINUTES 24 SECONDS EAST A DISTANCE OF 129.98 FEET TO A POINT ON THE ARC OF A NON-TANGENT CURVE WHOSE CENTER BEARS SOUTH 61 DEGREES 57 MINUTES 55 SECONDS EAST A DISTANCE OF 323.00 FEET, ALSO BEING A POINT ON THE NORTHERLY RIGHT OF WAY LINE OF THE HIGHLINE CANAL, AS RECORDED IN BOOK 122 OF DEEDS, PAGES 1 THROUGH 9, RECORDS OF MARICOPA COUNTY, ARIZONA;

THENCE ALONG SAID RIGHT OF WAY LINE THE FOLLOWING 6 COURSES:

THENCE ALONG THE ARC OF SAID NON-TANGENT CURVE THROUGH A CENTRAL ANGLE OF 7 DEGREES 35 MINUTES 20 SECONDS AND AN ARC LENGTH OF 42.78 FEET;

THENCE SOUTH 20 DEGREES 26 MINUTES 45 SECONDS WEST A DISTANCE OF 120.01 FEET TO THE BEGINNING OF A TANGENT CURVE WHOSE CENTER BEARS NORTH 69 DEGREES 33 MINUTES 15 SECONDS WEST A DISTANCE OF 187.90 FEET;

THENCE ALONG THE ARC OF SAID TANGENT CURVE THROUGH A CENTRAL ANGLE OF 58 DEGREES 34 MINUTES 01 SECONDS AND AN ARC LENGTH OF 192.07 FEET;

THENCE SOUTH 79 DEGREES 00 MINUTES 46 SECONDS WEST A DISTANCE OF 366.74 FEET TO THE BEGINNING OF A TANGENT CURVE WHOSE CENTER BEARS NORTH 10 DEGREES 59 MINUTES 14 SECONDS WEST A DISTANCE OF 158.18 FEET;

THENCE ALONG THE ARC OF SAID TANGENT CURVE THROUGH A CENTRAL ANGLE OF 56 DEGREES 46 MINUTES 19 SECONDS AND AN ARC LENGTH OF 156.73 FEET;

THENCE NORTH 44 DEGREES 12 MINUTES 55 SECONDS WEST A DISTANCE OF 176.41 FEET TO THE BEGINNING OF A TANGENT CURVE WHOSE CENTER BEARS SOUTH 45 DEGREES 47 MINUTES 05 SECONDS WEST A DISTANCE OF 228.18 FEET;

THENCE ALONG THE ARC OF SAID TANGENT CURVE THROUGH A CENTRAL ANGLE OF 50 DEGREES 23 MINUTES 19 SECONDS AND AN ARC LENGTH OF 200.67 FEET;

THENCE SOUTH 85 DEGREES 23 MINUTES 46 SECONDS WEST A DISTANCE OF 123.36 FEET;

THENCE SOUTH 89 DEGREES 19 MINUTES 11 SECONDS WEST A DISTANCE OF 70.30 FEET;

THENCE NORTH 00 DEGREES 28 MINUTES 46 SECONDS EAST A DISTANCE OF 144.59 FEET TO THE BEGINNING OF A TANGENT CURVE WHOSE CENTER BEARS NORTH 89 DEGREES 31 MINUTES 14 SECONDS WEST A DISTANCE OF 117.87 FEET;

THENCE ALONG THE ARC OF SAID TANGENT CURVE THROUGH A CENTRAL ANGLE OF 46 DEGREES 01 MINUTES 50 SECONDS AND AN ARC LENGTH OF 114.78 FEET;

THENCE NORTH 45 DEGREES 31 MINUTES 27 SECONDS WEST A DISTANCE OF 47.96 FEET TO A POINT ON THE ARC OF A NON-TANGENT CURVE WHOSE CENTER BEARS NORTH 45 DEGREES 26 MINUTES 34 SECONDS WEST A DISTANCE OF 500.00 FEET;


THENCE ALONG THE ARC OF SAID NON-TANGENT CURVE THROUGH A CENTRAL ANGLE OF 27 DEGREES 14 MINUTES 28 SECONDS AND AN ARC LENGTH OF 237.80 FEET TO THE POINT OF BEGINNING.

TRACT TABLE		
TRACT	AREA	USE
"A"	125,151 SF. 2.8731 AC.	PRIVATE ACCESSWAY, PUBLIC WATER & SEWER, DRAINAGE, REFUSE COLLECTION, AND EMERGENCY AND SERVICE VEHICLE
"B"	6,015 SF. 0.1381 AC.	LANDSCAPING, P.U.E., RETENTION AND OPEN SPACE
"C"	24,548 SF. 0.5635 AC.	LANDSCAPING, PEDESTRIAN ACCESS, P.U.E., RETENTION AND OPEN SPACE
"D"	34,116 SF. 0.7832 AC.	LANDSCAPING, PEDESTRIAN ACCESS, P.U.E., RETENTION AND OPEN SPACE
"E"	1,853 SF. 0.0425 AC.	LANDSCAPING, PEDESTRIAN ACCESS, AND P.U.E.
"F"	2,840 SF. 0.0652 AC.	LANDSCAPING, PEDESTRIAN ACCESS, AND P.U.E.
"G"	85,898 SF. 1.9719 AC.	LANDSCAPING, PEDESTRIAN ACCESS, P.U.E., DRAINAGE AND OPEN SPACE
"H"	14,180 SF. 0.3255 AC.	LANDSCAPING, PEDESTRIAN ACCESS, P.U.E., RETENTION AND OPEN SPACE
"I"	21,250 SF. 0.4878 AC.	LANDSCAPING, PEDESTRIAN ACCESS, P.U.E., RETENTION AND OPEN SPACE
"J"	49,873 SF. 1.1449 AC.	LANDSCAPING, PEDESTRIAN ACCESS, P.U.E., AND OPEN SPACE
TOTAL	365,724 SF. 8.3959 AC.	

# PRELIMINARY SITE PLAN FOR PRESERVE AT THE HIGHLINE

"A DETACHED SINGLE FAMILY PLANNED RESIDENTIAL DEVELOPMENT  
SUBDIVISION SUBJECT TO HILLSIDE AND SINGLE FAMILY DESIGN REVIEW"

SITUATED IN A PORTION OF THE NORTHEAST QUARTER OF SECTION 1, TOWNSHIP 1 SOUTH,  
RANGE 3 EAST, OF THE GILA & SALT RIVER BASE AND MERIDIAN, MARICOPA COUNTY, ARIZONA



PROJECT DATA PRESERVE AT THE HIGHLINE	
SECTION 613 ZONING: R1-6 DEVELOPMENT OPTION: P.R.D. - TABLE A SUBJECT TO BASELINE AREA OVERLAY	
STANDARDS	PROVIDED
MINIMUM LOT WIDTH (IN THE EVENT OF HORIZONTAL PROPERTY REGIMES, "LOT" SHALL REFER TO THE WIDTH OF THE STRUCTURE AND EXCLUSIVE USE AREA) *7	45' MINIMUM
MINIMUM LOT DEPTH	76' MINIMUM
DWELLING UNIT DENSITY (UNITS/GROSS ACRE)	3.39
MINIMUM PERIMETER BUILDING SETBACKS	STREET (FRONT, REAR OR SIDE): 15' (IN ADDITION TO LANDSCAPE SETBACK); PROPERTY LINE (REAR): 15' (1-STORY), 20' (2-STORY); PROPERTY LINE (SIDE): 10' (1-STORY), 15' (2-STORY)
COMMON LANDSCAPED SETBACK ADJACENT TO PERIMETER STREETS	15'
MINIMUM INTERIOR BUILDING SETBACKS	FRONT: 10'; REAR: NONE (ESTABLISHED BY BUILDING CODE); STREET SIDE: 10'; SIDES: NONE (ESTABLISHED BY BUILDING CODE)
MINIMUM BUILDING SEPARATION	10' (PER BASELINE AREA OVERLAY DISTRICT GUIDELINES)
MINIMUM GARAGE SETBACK	18' FROM BACK OF SIDEWALK FOR FRONT-LOADED GARAGES, 10' FROM PROPERTY LINE FOR SIDE-LOADED
MAXIMUM GARAGE WIDTH	FOR LOTS <60': 2 CAR WIDTHS
MAXIMUM HEIGHT	2 STORIES AND 30'
LOT COVERAGE	PRIMARY STRUCTURE, NOT INCLUDING ATTACHED SHADE STRUCTURES: 40% TOTAL: 50%
COMMON AREAS	26% OF GROSS AREA
ALLOWED USES	SINGLE-FAMILY DETACHED
REQUIRED REVIEW	SINGLE FAMILY DESIGN REVIEW
STREET STANDARDS	PRIVATE ACCESSWAY
ON-LOT AND COMMON RETENTION	COMMON RETENTION
LANDSCAPE STANDARDS	PERIMETER COMMON: TREES SPACED A MAXIMUM OF 20-30 FEET ON CENTER (BASED ON SPECIES) OR IN EQUIVALENT GROUPINGS, AND 5 SHRUBS PER TREE

**ENGINEER**

CLOUSE ENGINEERING, INC.  
5010 E. SHEA BLVD., #110  
SCOTTSDALE, AZ 85254  
(602) 395-9300  
CONTACT: JEFF GILES  
EMAIL: JGILES@CLOUSEAZ.COM

**DEVELOPER**


PORCHLIGHT HOMES  
2915 E. BASELINE ROAD  
SUITE 118  
GILBERT, AZ 85234  
(480) 813-1324  
CONTACT: RYAN LARSEN

**PROJECT DESCRIPTION**

A 61 LOT SINGLE-FAMILY DEVELOPMENT WITHIN THE R1-6 P.R.D. ZONING DISTRICT.

**PARKING CALCULATIONS**

EACH LOT PROVIDED WITH A TWO (2) CAR GARAGE AND MINIMUM 18' DEEP DRIVEWAY



**LEGEND**

- INDICATES SUBDIVISION CORNER
- INDICATES FIRE HYDRANT
- INDICATES PUBLIC UTILITY EASEMENT AT ALL LOT FRONTAGE UNLESS OTHERWISE NOTED
- B.S.L. INDICATES MINIMUM BUILDING SETBACK LINES
- P.U.E. INDICATES PUBLIC UTILITY EASEMENT
- P.A.E. INDICATES PUBLIC ACCESS EASEMENT
- V.N.A.E. INDICATES VEHICULAR NON ACCESS EASEMENT

**SITE DATA**

EXISTING ZONING: S-1  
PROPOSED ZONING: R1-6 P.R.D.  
GROSS ACRES: 18.0190 ACRES OR 784,906 S.F.  
NET ACRES: 17.6784 ACRES OR 770,072 S.F.  
TOTAL NUMBER OF LOTS: 61  
PROPOSED DENSITY: 3.39 D.U. PER ACRE  
DENSITY CALCULATION: (# OF LOTS/GROSS ACRES - 61/18.02=3.39)  
TYPICAL LOT SIZE: 55'x100'  
BUILDING HEIGHT: 2 STORIES AND 30'  
LOT SALES: YES  
COMMON RETENTION  
PARCEL(S): 301-20-001, 301-20-007C, 301-20-010G, 301-20-010J, 301-20-049B, 301-20-050, 301-23-003C AND 301-23-003F

WATER, SEWER, AND SANITATION SERVICES BY THE CITY OF PHOENIX. ELECTRIC SERVICE BY S.R.P.  
GAS SERVICE BY SOUTHWEST GAS CORPORATION.  
TELEPHONE SERVICE BY CENTURYLINK  
CONSTRUCTION WITHIN PUBLIC UTILITY EASEMENT SHALL BE LIMITED TO UTILITIES, AND WOOD, WIRE OR REMOVABLE SECTION TYPE FENCING.  
ALL UTILITIES AND SINGLE PHASE ELECTRIC LINES ARE TO BE INSTALLED UNDERGROUND.  
40' MAXIMUM HEIGHT FOR TRANSFORMERS, CABINETS, AND OTHER EQUIPMENT WITHIN PERIMETER STREET FRONTAGES.

**LOT COVERAGE**

CALCULATION:  

$$\frac{\text{MAX. COVERAGE (\%)} \times \left( \frac{\text{NET AREA} - \text{STREET AREA}}{\text{# OF LOTS (PLUS 1 FOR OPEN SPACE)}} \right)}{62} = \text{MAX. ALLOWABLE AREA UNDER ROOF PER LOT}$$

$$\frac{(0.40) \left( \frac{17,6784 - 2,8731}{2,8731} \right) (43,560)}{62} = 4,161 \text{ S.F. MAXIMUM ALLOWABLE AREA PER LOT (ENCLOSED STRUCTURES)}$$

$$\frac{(0.10) \left( \frac{17,6784 - 2,8731}{2,8731} \right) (43,560)}{62} = 1,040 \text{ S.F. MAXIMUM ALLOWABLE AREA PER LOT (SHADE STRUCTURES)}$$






**OPEN SPACE**

GROSS ACRES: 18.0190 AC. OR 784,906 S.F. x .05 = 39,245 S.F. REQUIRED (MINIMUM 5% OF GROSS AREA REQUIRED) \* 207,861 S.F. PROVIDED \* (EXCLUDES AREA WITHIN LANDSCAPE SETBACK)

Revised

Date  
04-12-24  
As-Built  
Job No.  
230703

KIVA #23-1343  
SDEV #2300334  
Q.S. 01-36  
PAPP #2306597



**Clouse Engineering, Inc.**  
ENGINEERS - SURVEYORS  
5010 E. Shea Blvd Suite 110 Scottsdale, AZ 85254  
Tel: 602-395-9300 Fax: 602-395-9310

**PRELIMINARY SITE PLAN**  
**PRESERVE AT THE HIGHLINE**  
**AN R1-6 PLANNED RESIDENTIAL DEVELOPMENT**  
PHOENIX ARIZONA

Revised  
Date 04-12-24  
As-Built  
Job No. 230703  
KIVA #23-1343  
SDEV #2300334  
Q.S. 01-36  
PAPP #2306597




Tab 4

# THE PRESERVE AT THE HIGHLINE


## PHOENIX, ARIZONA

5/30/2024







FLOOR PLAN



FRONT ELEVATION



REAR ELEVATION



LEFT ELEVATION

RIGHT ELEVATION


# THE PRESERVE AT THE HIGHLINE

PORCHLIGHT HOMES

COPYRIGHT © 2024 - WARNING AND NOTICE OF RIGHTS - THIS WORK IS PROTECTED UNDER U.S. COPYRIGHT LAW. These plans may not be copied, in whole or in part, nor otherwise reproduced, changed or relied upon to create derivative or further works without the express, prior written permission. Infringements of works shall be prosecuted to the full extent of the law.

PLAN 1  
1,901 S.F.  
ELEVATION A - SANTA BARBARA CONTEMPORARY

LINDEROTH ASSOCIATES, INC.




FLOOR PLAN



FRONT ELEVATION



REAR ELEVATION



LEFT ELEVATION


RIGHT ELEVATION

# THE PRESERVE AT THE HIGHLINE

PORCHLIGHT HOMES

COPYRIGHT © 2024 - WARNING AND NOTICE OF RIGHTS - THIS WORK IS PROTECTED UNDER U.S. COPYRIGHT LAW. These plans may not be copied, in whole or in part, nor otherwise reproduced, changed or relied upon to create derivative or further works without the express, prior written permission. Infringements of works shall be prosecuted to the full extent of the law.


PLAN 1  
1,901 S.F.  
ELEVATION B - DESERT PRAIRIE  
LINDEROTH ASSOCIATES, INC.




FLOOR PLAN



FRONT ELEVATION



REAR ELEVATION



LEFT ELEVATION

RIGHT ELEVATION




# THE PRESERVE AT THE HIGHLINE

PORCHLIGHT HOMES

COPYRIGHT © 2024 - WARNING AND NOTICE OF RIGHTS - THIS WORK IS PROTECTED UNDER U.S. COPYRIGHT LAW. These plans may not be copied, in whole or in part, nor otherwise reproduced, changed or relied upon to create derivative or further works without the express, prior written permission. Infringements of works shall be prosecuted to the full extent of the law.

PLAN 1  
1,901 S.F.  
ELEVATION C - MID-CENTURY MODERN

LINDEROTH ASSOCIATES, INC.






# THE PRESERVE AT THE HIGHLINE

PORCHLIGHT HOMES

COPYRIGHT © 2024 - WARNING AND NOTICE OF RIGHTS - THIS WORK IS PROTECTED UNDER U.S. COPYRIGHT LAW. These plans may not be copied, in whole or in part, nor otherwise reproduced, changed or relied upon to create derivative or further works without the express, prior written permission. Infringements of works shall be prosecuted to the full extent of the law.

PLAN 2  
2,887 S.F.  
ELEVATION A - SANTA BARBARA CONTEMPORARY

LINDEROTH ASSOCIATES, INC.



# THE PRESERVE AT THE HIGHLINE


PORCHLIGHT HOMES

COPYRIGHT © 2024 - WARNING AND NOTICE OF RIGHTS - THIS WORK IS PROTECTED UNDER U.S. COPYRIGHT LAW. These plans may not be copied, in whole or in part, nor otherwise reproduced, changed or relied upon to create derivative or further works without the express, prior written permission. Infringements of works shall be prosecuted to the full extent of the law.

PLAN 2  
2,887 S.F.  
ELEVATION B - DESERT PRAIRIE  
LINDEROTH ASSOCIATES, INC.




UPPER FLOOR PLAN




FLOOR PLAN



FRONT ELEVATION



REAR ELEVATION



LEFT ELEVATION

RIGHT ELEVATION

# THE PRESERVE AT THE HIGHLINE


PORCHLIGHT HOMES

COPYRIGHT © 2024 - WARNING AND NOTICE OF RIGHTS - THIS WORK IS PROTECTED UNDER U.S. COPYRIGHT LAW. These plans may not be copied, in whole or in part, nor otherwise reproduced, changed or relied upon to create derivative or further works without the express, prior written permission. Infringements of works shall be prosecuted to the full extent of the law.

PLAN 2  
2,887 S.F.  
ELEVATION C - MID-CENTURY MODERN

LINDEROTH ASSOCIATES, INC.






UPPER FLOOR PLAN




FLOOR PLAN

- CONCRETE ROOF TILE
- SAND FINISH STUCCO
- DECORATIVE TILE
- ACCENT W/ SAND FINISH STUCCO




- WOOD FASCIA
- SECTIONAL GARAGE DOOR
- DECORATIVE COACH LIGHT

FRONT ELEVATION



REAR ELEVATION



LEFT ELEVATION

RIGHT ELEVATION


# THE PRESERVE AT THE HIGHLINE

PORCHLIGHT HOMES

COPYRIGHT © 2024 - WARNING AND NOTICE OF RIGHTS - THIS WORK IS PROTECTED UNDER U.S. COPYRIGHT LAW. These plans may not be copied, in whole or in part, nor otherwise reproduced, changed or relied upon to create derivative or further works without the express, prior written permission. Infringements of works shall be prosecuted to the full extent of the law.

PLAN 3  
3,047 S.F.  
ELEVATION A - SANTA BARBARA CONTEMPORARY


LINDEROTH ASSOCIATES, INC.




UPPER FLOOR PLAN




FLOOR PLAN



FRONT ELEVATION



REAR ELEVATION



LEFT ELEVATION


RIGHT ELEVATION

# THE PRESERVE AT THE HIGHLINE

PORCHLIGHT HOMES

COPYRIGHT © 2024 - WARNING AND NOTICE OF RIGHTS - THIS WORK IS PROTECTED UNDER U.S. COPYRIGHT LAW. These plans may not be copied, in whole or in part, nor otherwise reproduced, changed or relied upon to create derivative or further works without the express, prior written permission. Infringements of works shall be prosecuted to the full extent of the law.

PLAN 3  
3,047 S.F.  
ELEVATION B - DESERT PRAIRIE  
LINDEROTH ASSOCIATES, INC.



UPPER FLOOR PLAN



FLOOR PLAN

DECORATIVE STONE VENEER  
 ACCENT W/ SAND FINISH STUCCO  
 SAND FINISH STUCCO




CONCRETE ROOF TILE  
 DECORATIVE COACH LIGHT  
 SECTIONAL GARAGE DOOR  
 W/ WINDOWS

FRONT ELEVATION



CONCRETE ROOF TILE  
 WOOD FASCIA  
 SAND FINISH STUCCO

REAR ELEVATION



CONCRETE ROOF TILE  
 DECORATIVE STONE VENEER  
 SAND FINISH STUCCO

LEFT ELEVATION

RIGHT ELEVATION

# THE PRESERVE AT THE HIGHLINE

PORCHLIGHT HOMES

COPYRIGHT © 2024 - WARNING AND NOTICE OF RIGHTS - THIS WORK IS PROTECTED UNDER U.S. COPYRIGHT LAW. These plans may not be copied, in whole or in part, nor otherwise reproduced, changed or relied upon to create derivative or further works without the express, prior written permission. Infringements of works shall be prosecuted to the full extent of the law.

PLAN 3  
 3,047 S.F.  
 ELEVATION C - MID-CENTURY MODERN

LINDEROTH ASSOCIATES, INC.

Santa Barbara Contemporary			
	Scheme A-1	Scheme A-2	Scheme A-3
Roof Tile: Eagle Roofing Capistrano			
	8403 Santa Barbara Blend	8403 Santa Barbara Blend	8403 Santa Barbara Blend
Stucco Body			
	SW 7636 Origami White	SW 7035 Aesthetic White	SW 6378 Crisp Linen
Popout/ Recesses/ Fascia/ Trim			
	SW 7675 Sealskin	SW 7018 Dovetail	SW 7069 Iron Ore
Garage Door			
	SW 7675 Sealskin	SW 7018 Dovetail	SW 7069 Iron Ore
Entry Door			
	SW 6472 Composed	SW 6230 Rainstorm	SW 6327 Bold Brick

Desert Prairie			
	Scheme B-1	Scheme B-2	Scheme B-3
Roof Tile: Eagle Roofing Bel Air			
	SCB 8828 Bridgeport Blend	SCB 8828 Bridgeport Blend	SCB 8828 Bridgeport Blend
Stucco Body			
	SW 7632 Modern Gray	SW 7015 Repose Gray	SW 9173 Shitake
Popout/ Recesses/ Fascia/ Trim			
	SW 7048 Urbane Bronze	SW 7069 Iron Ore	SW 9175 Deep Forest Brown
Garage Door/ Entry Door & Shutters			
	SW 7040 Smokehouse	SW 7019 Gauntlet Gray	SW 7509 Tiki Hut
Masonry (Creative Mines)			
	Craft Split Modular Sea Pearl	Craft Split Modular Sea Pearl	Craft Split Modular Sea Pearl

Mid-Century Modern			
	Scheme C-1	Scheme C-2	Scheme C-3
Roof Tile: Eagle Roofing Bel Air			
	4511 Flintridge Gray	4511 Flintridge Gray	4511 Flintridge Gray
Stucco Body			
	SW 7010 White Duck	SW 7043 Worldly Gray	SW 7051 Analytical Gray
Stucco Body Accent			
	SW 7060 Attitude Gray	SW 7642 Paverstone	SW 7053 Adaptive Shade
Popout/ Recesses/ Fascia/ Trim			
	SW 7645 Thunder Gray	SW 7675 Sealskin	SW 7055 Enduring Bronze
Garage Door			
	SW 7645 Thunder Gray	SW 7675 Sealskin	SW 7055 Enduring Bronze
Entry Door & Shutters			
	SW 0032 Needlepoint Navy	SW 2831 Classic Gold	SW 7710 Brandywine
Masonry (Coronado Stone)			
	3" Split Limestone White	3" Split Limestone White	3" Split Limestone White

**PROJECT NOTES**

\* TRIM: INCLUDES ANY WOOD FASCIA, TAILS, OR BRACES, OVERHANG, CORBELS. ALL HEADERS, SILLS, SURROUNDS & RECESSES AT ALL WINDOWS, DOORS AND GARAGES. ALSO INCLUDES POP-OUT CAPS ON STONE AND BRICK VENEER.  
 ALL WINDOWS TO BE WHITE  
 BRICK INSTALLATION: BRICK SHOULD BE INSTALLED WITH RELATIVELY TIGHT AND SLIGHTLY RECESSED JOINTS. ALLOW GROUT TO SET UP SLIGHTLY, THEN WIPED WITH A WET SPONGE TO EXPOSE THE SAND. BEING CAREFUL TO STAY IN GROUT LINE AND NOT OBSCURE THE BRICK FACES WITH GROUT.  
 STONE INSTALLATION: STONE TO BE SET TIGHT, JOINTS TO BE RECESSED, WITH GROUT ALLOWED TO SETUP SLIGHTLY THEN SPONGED TO REVEAL SAND.  
 O'HAGIN ROOF VENTS: PAINT TO MATCH DEEPER EDGE OF ROOF BLEND  
 SHAKE ROOF TILE SHOULD BE DETAILED WITHOUT THE USE OF GABLE-END PIECES.  
 COLORS ARE SHERWIN WILLIAMS, PER CLIENT'S DESIGNATION.

# THE PRESERVE AT THE HIGHLINE

ORDINANCE G-7243

AN ORDINANCE AMENDING THE ZONING DISTRICT MAP ADOPTED PURSUANT TO SECTION 601 OF THE CITY OF PHOENIX ZONING ORDINANCE BY CHANGING THE ZONING DISTRICT CLASSIFICATION FOR THE PARCEL DESCRIBED HEREIN (Z-104-23-8) FROM R1-6 BAOD (APPROVED R1-10 BAOD) (SINGLE-FAMILY RESIDENCE DISTRICT, BASELINE AREA OVERLAY DISTRICT, APPROVED SINGLE-FAMILY RESIDENCE DISTRICT, BASELINE AREA OVERLAY DISTRICT), S-1 BAOD (APPROVED R1-10 BAOD) (RANCH OR FARM RESIDENCE, BASELINE AREA OVERLAY DISTRICT, APPROVED SINGLE-FAMILY RESIDENCE DISTRICT, BASELINE AREA OVERLAY DISTRICT), AND S-1 BAOD (RANCH OR FARM RESIDENCE, BASELINE AREA OVERLAY DISTRICT) TO R1-6 BAOD (SINGLE-FAMILY RESIDENCE DISTRICT, BASELINE AREA OVERLAY DISTRICT).

---

BE IT ORDAINED BY THE COUNCIL OF THE CITY OF PHOENIX, as follows:

SECTION 1. The zoning of an 18.52-acre site located at the northeast corner of 36th Street and Beverly Road in a portion of Section 1, Township 1 South, Range 3 East, as described more specifically in Exhibit "A," is hereby changed from 0.83 acres of "R1-6 BAOD (Approved R1-10 BAOD)" (Single-Family Residence District, Baseline Area Overlay District, Approved Single-Family Residence District, Baseline Area Overlay District), 6.74 acres of "S-1 BAOD (Approved R1-10 BAOD)" (Ranch or

Farm Residence, Baseline Area Overlay District, Approved Single-Family Residence District, Baseline Area Overlay District), and 10.95 acres of "S-1 BAOD" (Ranch or Farm Residence, Baseline Area Overlay District) to "R1-6 BAOD" (Single-Family Residence District, Baseline Area Overlay District).

SECTION 2. The Planning and Development Director is instructed to modify the Zoning Map of the City of Phoenix to reflect this use district classification change as shown in Exhibit "B."

SECTION 3. Due to the site's specific physical conditions and the use district applied for by the applicant, this rezoning is subject to the following stipulations, violation of which shall be treated in the same manner as a violation of the City of Phoenix Zoning Ordinance:

1. Tracts "C", "H", "I", and "G", as generally depicted on the site plan date stamped January 17, 2024, shall be reserved for open space, as modified by the following stipulations, and approved by the Planning and Development Department.
2. The undisturbed hillside area (above 10% per the approved Slope Analysis) shall remain undisturbed and be dedicated with a preservation easement except for Lot 27 and development of private accessways as generally depicted on the site plan date stamped January 17, 2024, as approved by the Planning and Development Department.
3. The existing home on Lot 27 shall remain and any improvements to this lot shall be reviewed and approved through a Hillside/Grading and Drainage Plan by the Planning and Development Department.
4. A physical feature (such as retaining wall, rock wall, etc.) shall be provided along the west and south portions of Tract "J", as generally depicted on the site plan date stamped January 17, 2024, to protect the undisturbed hillside area, as approved by the Planning and Development Department.

5. A minimum of three distinct exterior accent materials for each required standard plan within the subdivision shall be provided, as approved by the Planning and Development Department.
6. If fencing is proposed along the perimeter of the site, the fencing shall be a minimum of 75% view fencing, except on Lots 1, 50, 51, 52, and 53 as depicted on the site plan date stamped January 17, 2024, as approved by the Planning and Development Department. Any perimeter fencing requirement adjacent to the Highline Canal is subject to review and approval of SRP.
7. All landscape setbacks shall be planted with minimum 2-inch caliper large canopy drought-tolerant trees, 20 feet on center or in equivalent groupings, with five 5-gallon shrubs per tree, as approved by the Planning and Development Department.
8. A minimum of 10% of the required shrubs, shall be a milkweed or other native nectar species, and shall be planted in groups of three or more and maintained, as approved by the Planning and Development Department.
9. The sidewalk along 36th Street shall be a minimum of five feet in width and detached with a minimum five-foot wide landscape strip located between the sidewalk and back of curb and planted to the following standards, as approved by the Planning and Development Department.
  - a. Minimum 2-inch caliper, single-trunk, large canopy, drought-tolerant shade trees planted 20 feet on center or in equivalent groupings.
  - b. Drought tolerant vegetation to achieve a minimum of 75 percent live coverage at maturity.

Where utility conflicts exist, the developer shall work with the Planning and Development Department on alternative design solutions consistent with a pedestrian environment for installing the required plants.

10. Prior to preliminary plat approval, documentation shall be provided that demonstrates participation in the Environmental Protection Agency's WaterSense certification program, or an equivalent program, as approved by the Planning and Development and Water Services departments.

11. A WaterSense inspection report from a third-party verifier shall be submitted that demonstrates successful participation in the Environmental Protection Agency's WaterSense certification program, or an equivalent program, prior to certificate of occupancy, as approved by the Planning and Development Department.
12. In addition to the landscape materials listed in the Baseline Area Master Plan Plant List Cercidium Hybrid (Desert Museum Palo Verde), Quercus Virginiana (Live Oak), And Pistacia X 'Red-Push (Red Push Pistache), may be permitted as approved by Planning and Development Department and shall be utilized throughout the subdivision including the front, side, and rear yards of individual residential lots. This restriction shall be included in the Covenants, Conditions, and Restrictions for the subdivision.
13. Landscaping in common areas shall be maintained by permanent and automatic/water efficient WaterSense labeled irrigation controllers (Smart Controller) to minimize maintenance and irrigation water consumption for all on and offsite landscape irrigation.
14. Pressure regulating sprinkler heads and drip lines shall be utilized in any turf areas to reduce water waste.
15. Natural turf shall only be utilized on individual single-family lots (behind the front yard); required retention areas (bottom of basin), and functional turf areas within common areas, as approved by the Planning and Development Department.
16. A minimum of two green infrastructure (GI) techniques for stormwater management shall be implemented per the Greater Phoenix Metro Green Infrastructure and Low-Impact Development Details for Alternative Stormwater Management, as approved or modified by the Planning and Development Department.
17. Swimming pools on individual single-family lots shall be limited to 600 square feet in size.
18. A public connection to the existing 36th Way stub street shall be provided or the existing 36th Way right-of-way shall be terminated per the City of Phoenix termination standards, as required by the Street Transportation Department.



19. An enhanced connection shall be provided on the southern site boundary to allow for direct pedestrian access to the adjacent Highline Canal. The developer shall construct an 8-foot-wide shaded pedestrian pathway consisting of decorative material such as brick, pavers or alternative material providing at the entryway, as approved by the Planning and Development Department.
20. A sidewalk easement shall be dedicated over a clearly defined pedestrian pathway(s) providing a public connection through the site from the existing 36th Way access point on the northern site boundary to the Highline Canal and the adjacent wash/trail system, as approved by the Planning and Development Department.
21. Replace unused driveways with sidewalk, curb, and gutter. Also, replace any broken or out-of-grade curb, gutter, sidewalk, curb ramps on all streets and upgrade all off-site improvements to be in compliance with current ADA guidelines.
22. All streets within and adjacent to the development shall be constructed with paving, curb, gutter, sidewalk, curb ramps, streetlights, median islands, landscaping and other incidentals, as per plans approved by the Planning and Development Department. All improvements shall comply with all ADA accessibility standards
23. The property owner shall record documents that disclose the existence, and operational characteristics of Phoenix Sky Harbor Airport to future owners or tenants of the property. The form and content of such documents shall be according to the templates and instructions provided which have been reviewed and approved by the City Attorney.
24. If determined necessary by the Phoenix Archaeology Office, the applicant shall conduct Phase I data testing and submit an archaeological survey report of the development area for review and approval by the City Archaeologist prior to clearing and grubbing, landscape salvage, and/or grading approval.
25. If Phase I data testing is required, and if, upon review of the results from the Phase I data testing, the City Archaeologist, in consultation with a qualified archaeologist, determines such data recovery excavations are necessary, the applicant shall conduct Phase II archaeological data recovery excavations.

26. In the event archaeological materials are encountered during construction, the developer shall immediately cease all ground-disturbing activities within a 33-foot radius of the discovery, notify the City Archaeologist, and allow time for the Archaeology Office to properly assess the materials.
27. Prior to final site plan approval, the landowner shall execute a Proposition 207 waiver of claims form. The waiver shall be recorded with the Maricopa County Recorder's Office and delivered to the City to be included in the rezoning application file for record.
28. Bench seating shall be provided near the western pedestrian connection, located between Lots 39 and 50, as depicted on the site plan date stamped January 17, 2024, and as approved by the Planning and Development Department.
29. At least 50% of the residential homes abutting the canal (Lots 28 through 39, as depicted on the site plan date stamped January 17, 2024) shall be a maximum of one story or 15 feet in height, as approved by the Planning and Development Department.
30. The developer shall provide evidence of undertaking reasonable efforts to work with the adjacent homeowners association to the north, to close off the former access drive east of the "Groves at Baseline" subdivision by installing a solid 4-foot tall block wall with a 2-foot view fence atop, at the northeast corner of the site and at the driveway entrance along Baseline Road, with a locked access gate on the south end for maintenance as needed.
31. A Traffic Impact Analysis (TIA) shall be submitted to the City for this development. No preliminary approval of plans shall be granted until the analysis is reviewed and approved by the Street Transportation Department. The TIA shall include a signal warrant analysis for 36th Street and Baseline Road. If the approved TIA determines that a signal is warranted and is approved by the Street Transportation Department for installation, the developer shall be responsible for its proportionate share of the funding and construction of all recommendations of the analysis.
32. The subdivision shall have no more than 61 lots.

33. On-site lighting within open space areas shall be accomplished with low level, uniform light fixtures dispersed throughout the site with a lumen rating of 3,000 or less.

Mod


34. The conceptual elevations for future development (new homes) shall be reviewed and approved, with specific regard to the Single-Family Design Review Guidelines, by the Planning Hearing Officer through the public hearing process, including review by the South Mountain Village Planning Committee, for stipulation modification prior to preliminary site plan approval. This is a legislative review for conceptual purposes only. Specific development standards and requirements will be determined by the Planning Hearing Officer, and the Planning and Development Department.

35. Any invasive plants shall not be allowed.

36. Native materials, or similar materials, shall be used for all exterior perimeter wall columns, as approved by the Planning and Development Department.

SECTION 4. If any section, subsection, sentence, clause, phrase or portion of this ordinance is for any reason held to be invalid or unconstitutional by the decision of any court of competent jurisdiction, such decision shall not affect the validity of the remaining portions hereof.

PASSED by the Council of the City of Phoenix this 3rd day of April, 2024.

  
MAYOR

4/5/2024


Date

ATTEST:

  
Denise Archibald, City Clerk



APPROVED AS TO FORM:  
Julie M. Kriegh, City Attorney

By: 

\_\_\_\_\_ P ml

REVIEWED BY:

  
\_\_\_\_\_  
Jeffrey Barton, City Manager

PML:ac:(LF24-0553):4-3-24:2427108\_1.doc

Exhibits:

- A – Legal Description (2 Pages)
- B – Ordinance Location Map (1 Page)

**EXHIBIT A**

LEGAL DESCRIPTION FOR Z-104-23-8

A portion of the North half of Section 1, Township 1 South, Range 3 East of the Gila and Salt River Base and Meridian, Maricopa County, Arizona, more particularly described as follows:

Commencing at the North quarter corner of said Section 1;

Thence along the West line of the Northeast quarter of said Section 1, South 00 degrees 31 minutes 29 seconds West a distance of 835.13 feet to the beginning of a non-tangent curve whose center bears North 89 degrees 28 minutes 44 seconds West a distance of 500.00 feet;

Thence along the arc of said non-tangent curve through a central angle of 16 degrees 47 minutes 26 seconds and an arc length of 146.52 feet to the POINT OF BEGINNING;

Thence South 72 degrees 41 minutes 18 seconds East a distance of 30.00 feet to a point on the Easterly right of way line of 36th Street;

Thence North 89 degrees 40 minutes 26 seconds East a distance of 527.92 feet;

Thence North 00 degrees 34 minutes 55 seconds East a distance of 332.04 feet;

Thence North 89 degrees 51 minutes 09 seconds East a distance of 464.64 feet to a point on the West property line of Blossom Hills, a subdivision, as recorded in Book 899 of Maps, Page 7, records of Maricopa County, Arizona;

Thence along said West line, South 00 degrees 31 minutes 34 seconds West a distance of 666.62 feet;

Thence North 89 degrees 58 minutes 24 seconds East a distance of 129.98 feet to a point on the arc of a non-tangent curve whose center bears South 61 degrees 57 minutes 55 seconds East a distance of 323.00 feet, also being a point on the Northerly right of way line of the Highline Canal, as recorded in Book 122 of Deeds, Pages 1 through 9, records of Maricopa County, Arizona;

This along said right of way line the following 6 courses:

Thence along the arc of said non-tangent curve through a central angle of 7 degrees 35 minutes 20 seconds and an arc length of 42.78 feet;

Thence South 20 degrees 26 minutes 45 seconds West a distance of 120.01 feet to the beginning of a tangent curve whose center bears North 69 degrees 33 minutes 15 seconds West a distance of 187.90 feet;

Thence along the arc of said tangent curve through a central angle of 58 degrees 34 minutes 01 seconds and an arc length of 192.07 feet;

Thence South 79 degrees 00 minutes 46 seconds West a distance of 366.74 feet to the beginning of a tangent curve whose center bears North 10 degrees 59 minutes 14 seconds West a distance of 158.18 feet;

Thence along the arc of said tangent curve through a central angle of 56 degrees 46 minutes 19 seconds and an arc length of 156.73 feet; Thence North 44 degrees 12 minutes 55 seconds West a distance of 176.41 feet to the beginning of a tangent curve whose center bears South 45 degrees 47 minutes 05 seconds West a distance of 228.18 feet;

Thence along the arc of said tangent curve through a central angle of 50 degrees 23 minutes 19 seconds and an arc length of 200.67 feet;

Thence South 85 degrees 23 minutes 46 seconds West a distance of 123.36 feet;

Thence South 89 degrees 19 minutes 11 seconds West a distance of 70.30 feet;

Thence North 00 degrees 28 minutes 46 seconds East a distance of 144.59 feet to the beginning of a tangent curve whose center bears North 89 degrees 31 minutes 14 seconds West a distance of 117.87 feet;

Thence along the arc of said tangent curve through a central angle of 46 degrees 01 minutes 50 seconds and an arc length of 114.78 feet;

Thence North 45 degrees 31 minutes 27 seconds West a distance of 47.96 feet to a point on the arc of a non-tangent curve whose center bears North 45 degrees 26 minutes 34 seconds West a distance of 500.00 feet;

Thence along the arc of said non-tangent curve through a central angle of 27 degrees 14 minutes 28 seconds and an arc length of 237.80 feet to the POINT OF BEGINNING.



Note: The above described parcel contains 784,908 square feet or 18.0190 acres, more or less.

**G7243**


# ORDINANCE LOCATION MAP

Zoning Case Number: Z-104-23-8  
 Zoning Overlay: Baseline Area Plan and Overlay District  
 Planning Village: South Mountain

ZONING SUBJECT TO STIPULATIONS: \*  
 SUBJECT AREA: - - - - -




NOT TO SCALE



PHO-1-24--Z-104-23-8

Property Location: Northeast corner of 36th Street and Beverly Road





mapservices@phoenix.gov

PHO-1-24--Z-104-23-8

Property Location: Northeast corner of 36th Street and Beverly Road



**NOTES**

- A. DEVELOPMENT AND USE OF THIS SITE WILL CONFORM TO ALL APPLICABLE CODES AND ORDINANCES.
- B. ALL NEW OR RELOCATED UTILITIES WILL BE PLACED UNDERGROUND
- C. ANY LIGHTING WILL BE PLACED SO AS TO DIRECT LIGHT AWAY FROM ADJACENT RESIDENTIAL DISTRICTS AND WILL NOT EXCEED ONE FOOT CANDLE AT THE PROPERTY LINE. NO NOISE, ODOR OR VIBRATION WILL BE EMITTED SO THAT IT EXCEEDS THE GENERAL LEVEL OF NOISE, ODOR, OR VIBRATION EMITTED BY USES OUTSIDE OF THE SITE.
- D. OWNERS OF PROPERTY ADJACENT TO PUBLIC RIGHT-OF-WAY WILL HAVE THE RESPONSIBILITY FOR MAINTAINING ALL LANDSCAPING WITHIN THE RIGHTS OF WAY, IN ACCORDANCE WITH APPROVED PLANS.
- E. ALL ROOFTOP EQUIPMENT AND SATELLITE DISHES SHALL BE SCREENED TO THE HEIGHT OF THE TALLEST EQUIPMENT.
- F. THIS PROJECT IS LOCATED IN THE CITY OF PHOENIX WATER SERVICE AREA AND HAS BEEN DESIGNATED AS HAVING AN ASSURED WATER SUPPLY.

I CONSENT TO THE REPRODUCTION OF THIS SITE PLAN PROVIDED THAT IF MODIFICATIONS ARE MADE, THE PROFESSIONALS WHO MAKE SUCH CHANGES ASSUME FULL RESPONSIBILITY AND LIABILITY FOR THE MODIFIED PORTIONS OF THE PLAN.

PRESIDENT	1-10-24
SIGNATURE OF COPYRIGHT OWNER	DATE
CLOUSE ENGINEERING, INC.	1-10-24
PRINT NAME OF COPYRIGHT OWNER	DATE

**LEGAL DESCRIPTION**

A PORTION OF THE NORTH HALF OF SECTION 1, TOWNSHIP 2 SOUTH, RANGE 3 EAST OF THE GILA AND SALT RIVER BASE AND MERIDIAN, MARICOPA COUNTY, ARIZONA, MORE PARTICULARLY DESCRIBED AS FOLLOWS:

COMMENCING AT THE NORTH QUARTER CORNER OF SAID SECTION 1;

THENCE ALONG THE WEST LINE OF THE NORTHEAST QUARTER OF SAID SECTION 1, SOUTH 00 DEGREES 31 MINUTES 29 SECONDS WEST A DISTANCE OF 835.13 FEET TO THE BEGINNING OF A NON-TANGENT CURVE WHOSE CENTER BEARS NORTH 89 DEGREES 28 MINUTES 44 SECONDS WEST A DISTANCE OF 500.00 FEET;

THENCE ALONG THE ARC OF SAID NON-TANGENT CURVE THROUGH A CENTRAL ANGLE OF 16 DEGREES 47 MINUTES 26 SECONDS AND AN ARC LENGTH OF 146.52 FEET TO THE POINT OF BEGINNING;

THENCE SOUTH 72 DEGREES 41 MINUTES 18 SECONDS EAST A DISTANCE OF 30.00 FEET TO A POINT ON THE EASTERLY RIGHT OF WAY LINE OF 36TH STREET;

THENCE NORTH 89 DEGREES 40 MINUTES 26 SECONDS EAST A DISTANCE OF 527.92 FEET;

THENCE NORTH 00 DEGREES 34 MINUTES 55 SECONDS EAST A DISTANCE OF 332.04 FEET;

THENCE NORTH 89 DEGREES 51 MINUTES 09 SECONDS EAST A DISTANCE OF 464.64 FEET TO A POINT ON THE WEST PROPERTY LINE OF BLOSSOM HILLS, A SUBDIVISION, AS RECORDED IN BOOK 899 OF MAPS, PAGE 7, RECORDS OF MARICOPA COUNTY, ARIZONA;

THENCE ALONG SAID WEST LINE, SOUTH 00 DEGREES 31 MINUTES 34 SECONDS WEST A DISTANCE OF 666.62 FEET;

THENCE NORTH 89 DEGREES 58 MINUTES 24 SECONDS EAST A DISTANCE OF 129.98 FEET TO A POINT ON THE ARC OF A NON-TANGENT CURVE WHOSE CENTER BEARS SOUTH 61 DEGREES 57 MINUTES 55 SECONDS EAST A DISTANCE OF 323.00 FEET, ALSO BEING A POINT ON THE NORTHERLY RIGHT OF WAY LINE OF THE HIGHLINE CANAL, AS RECORDED IN BOOK 122 OF DEEDS, PAGES 1 THROUGH 9, RECORDS OF MARICOPA COUNTY, ARIZONA;

THENCE ALONG SAID RIGHT OF WAY LINE THE FOLLOWING 6 COURSES:

THENCE ALONG THE ARC OF SAID NON-TANGENT CURVE THROUGH A CENTRAL ANGLE OF 7 DEGREES 35 MINUTES 20 SECONDS AND AN ARC LENGTH OF 42.78 FEET;

THENCE SOUTH 20 DEGREES 26 MINUTES 45 SECONDS WEST A DISTANCE OF 120.01 FEET TO THE BEGINNING OF A TANGENT CURVE WHOSE CENTER BEARS NORTH 69 DEGREES 33 MINUTES 15 SECONDS WEST A DISTANCE OF 187.90 FEET;

THENCE ALONG THE ARC OF SAID TANGENT CURVE THROUGH A CENTRAL ANGLE OF 58 DEGREES 34 MINUTES 01 SECONDS AND AN ARC LENGTH OF 192.07 FEET;

THENCE SOUTH 79 DEGREES 00 MINUTES 46 SECONDS WEST A DISTANCE OF 366.74 FEET TO THE BEGINNING OF A TANGENT CURVE WHOSE CENTER BEARS NORTH 10 DEGREES 59 MINUTES 14 SECONDS WEST A DISTANCE OF 158.18 FEET;

THENCE ALONG THE ARC OF SAID TANGENT CURVE THROUGH A CENTRAL ANGLE OF 56 DEGREES 46 MINUTES 19 SECONDS AND AN ARC LENGTH OF 156.73 FEET;

THENCE NORTH 44 DEGREES 12 MINUTES 55 SECONDS WEST A DISTANCE OF 176.41 FEET TO THE BEGINNING OF A TANGENT CURVE WHOSE CENTER BEARS SOUTH 45 DEGREES 47 MINUTES 05 SECONDS WEST A DISTANCE OF 228.18 FEET;

THENCE ALONG THE ARC OF SAID TANGENT CURVE THROUGH A CENTRAL ANGLE OF 50 DEGREES 23 MINUTES 19 SECONDS AND AN ARC LENGTH OF 200.67 FEET;

THENCE SOUTH 85 DEGREES 23 MINUTES 46 SECONDS WEST A DISTANCE OF 123.36 FEET;

THENCE SOUTH 89 DEGREES 19 MINUTES 11 SECONDS WEST A DISTANCE OF 70.30 FEET;

THENCE NORTH 00 DEGREES 28 MINUTES 46 SECONDS EAST A DISTANCE OF 144.59 FEET TO THE BEGINNING OF A TANGENT CURVE WHOSE CENTER BEARS NORTH 89 DEGREES 31 MINUTES 14 SECONDS WEST A DISTANCE OF 117.87 FEET;

THENCE ALONG THE ARC OF SAID TANGENT CURVE THROUGH A CENTRAL ANGLE OF 46 DEGREES 01 MINUTES 50 SECONDS AND AN ARC LENGTH OF 114.78 FEET;

THENCE NORTH 45 DEGREES 31 MINUTES 27 SECONDS WEST A DISTANCE OF 47.96 FEET TO A POINT ON THE ARC OF A NON-TANGENT CURVE WHOSE CENTER BEARS NORTH 45 DEGREES 26 MINUTES 34 SECONDS WEST A DISTANCE OF 500.00 FEET;


THENCE ALONG THE ARC OF SAID NON-TANGENT CURVE THROUGH A CENTRAL ANGLE OF 27 DEGREES 14 MINUTES 28 SECONDS AND AN ARC LENGTH OF 237.80 FEET TO THE POINT OF BEGINNING.

TRACT TABLE		
TRACT	AREA	USE
"A"	125,151 SF. 2.8731 AC.	PRIVATE ACCESSWAY, PUBLIC WATER & SEWER, DRAINAGE, REFUSE COLLECTION, AND EMERGENCY AND SERVICE VEHICLE
"B"	6,015 SF. 0.1381 AC.	LANDSCAPING, P.U.E., RETENTION AND OPEN SPACE
"C"	24,548 SF. 0.5635 AC.	LANDSCAPING, PEDESTRIAN ACCESS, P.U.E., RETENTION AND OPEN SPACE
"D"	34,116 SF. 0.7832 AC.	LANDSCAPING, PEDESTRIAN ACCESS, P.U.E., RETENTION AND OPEN SPACE
"E"	1,853 SF. 0.0425 AC.	LANDSCAPING, PEDESTRIAN ACCESS, AND P.U.E.
"F"	2,840 SF. 0.0652 AC.	LANDSCAPING, PEDESTRIAN ACCESS, AND P.U.E.
"G"	85,898 SF. 1.9719 AC.	LANDSCAPING, PEDESTRIAN ACCESS, P.U.E., DRAINAGE AND OPEN SPACE
"H"	14,180 SF. 0.3255 AC.	LANDSCAPING, PEDESTRIAN ACCESS, P.U.E., RETENTION AND OPEN SPACE
"I"	21,250 SF. 0.4878 AC.	LANDSCAPING, PEDESTRIAN ACCESS, P.U.E., RETENTION AND OPEN SPACE
"J"	49,873 SF. 1.1449 AC.	LANDSCAPING, PEDESTRIAN ACCESS, P.U.E., AND OPEN SPACE
TOTAL	365,724 SF. 8.3959 AC.	

# PRELIMINARY SITE PLAN FOR PRESERVE AT THE HIGHLINE

"A DETACHED SINGLE FAMILY PLANNED RESIDENTIAL DEVELOPMENT  
SUBDIVISION SUBJECT TO HILLSIDE AND SINGLE FAMILY DESIGN REVIEW"

SITUATED IN A PORTION OF THE NORTHEAST QUARTER OF SECTION 1, TOWNSHIP 1 SOUTH,  
RANGE 3 EAST, OF THE GILA & SALT RIVER BASE AND MERIDIAN, MARICOPA COUNTY, ARIZONA



PROJECT DATA PRESERVE AT THE HIGHLINE	
SECTION 613 ZONING: R1-6 DEVELOPMENT OPTION: P.R.D. - TABLE A SUBJECT TO BASELINE AREA OVERLAY	
STANDARDS	PROVIDED
MINIMUM LOT WIDTH (IN THE EVENT OF HORIZONTAL PROPERTY REGIMES, "LOT" SHALL REFER TO THE WIDTH OF THE STRUCTURE AND EXCLUSIVE USE AREA) *7	45' MINIMUM
MINIMUM LOT DEPTH	76' MINIMUM
DWELLING UNIT DENSITY (UNITS/GROSS ACRE)	3.39
MINIMUM PERIMETER BUILDING SETBACKS	STREET (FRONT, REAR OR SIDE): 15' (IN ADDITION TO LANDSCAPE SETBACK); PROPERTY LINE (REAR): 15' (1-STORY), 20' (2-STORY); PROPERTY LINE (SIDE): 10' (1-STORY), 15' (2-STORY)
COMMON LANDSCAPED SETBACK ADJACENT TO PERIMETER STREETS	15'
MINIMUM INTERIOR BUILDING SETBACKS	FRONT: 10'; REAR: NONE (ESTABLISHED BY BUILDING CODE); STREET SIDE: 10'; SIDES: NONE (ESTABLISHED BY BUILDING CODE)
MINIMUM BUILDING SEPARATION	10' (PER BASELINE AREA OVERLAY DISTRICT GUIDELINES)
MINIMUM GARAGE SETBACK	18' FROM BACK OF SIDEWALK FOR FRONT-LOADED GARAGES, 10' FROM PROPERTY LINE FOR SIDE-LOADED
MAXIMUM GARAGE WIDTH	FOR LOTS <60': 2 CAR WIDTHS
MAXIMUM HEIGHT	2 STORIES AND 30'
LOT COVERAGE	PRIMARY STRUCTURE, NOT INCLUDING ATTACHED SHADE STRUCTURES: 40% TOTAL: 50%
COMMON AREAS	26% OF GROSS AREA
ALLOWED USES	SINGLE-FAMILY DETACHED
REQUIRED REVIEW	SINGLE FAMILY DESIGN REVIEW
STREET STANDARDS	PRIVATE ACCESSWAY
ON-LOT AND COMMON RETENTION	COMMON RETENTION
LANDSCAPE STANDARDS	PERIMETER COMMON: TREES SPACED A MAXIMUM OF 20-30 FEET ON CENTER (BASED ON SPECIES) OR IN EQUIVALENT GROUPINGS, AND 5 SHRUBS PER TREE

**ENGINEER**

CLOUSE ENGINEERING, INC.  
5010 E. SHEA BLVD., #110  
SCOTTSDALE, AZ 85254  
(602) 395-9300  
CONTACT: JEFF GILES  
EMAIL: JGILES@CLOUSEAZ.COM

**DEVELOPER**


PORCHLIGHT HOMES  
2915 E. BASELINE ROAD  
SUITE 118  
GILBERT, AZ 85234  
(480) 813-1324  
CONTACT: RYAN LARSEN

**PROJECT DESCRIPTION**

A 61 LOT SINGLE-FAMILY DEVELOPMENT WITHIN THE R1-6 P.R.D. ZONING DISTRICT.

**PARKING CALCULATIONS**

EACH LOT PROVIDED WITH A TWO (2) CAR GARAGE AND MINIMUM 18' DEEP DRIVEWAY



**LEGEND**

- INDICATES SUBDIVISION CORNER
- INDICATES FIRE HYDRANT
- INDICATES PUBLIC UTILITY EASEMENT AT ALL LOT FRONTAGE UNLESS OTHERWISE NOTED
- B.S.L. INDICATES MINIMUM BUILDING SETBACK LINES
- P.U.E. INDICATES PUBLIC UTILITY EASEMENT
- P.A.E. INDICATES PUBLIC ACCESS EASEMENT
- V.N.A.E. INDICATES VEHICULAR NON ACCESS EASEMENT

**SITE DATA**

EXISTING ZONING: S-1  
PROPOSED ZONING: R1-6 P.R.D.  
GROSS ACRES: 18.0190 ACRES OR 784,906 S.F.  
NET ACRES: 17.6784 ACRES OR 770,072 S.F.  
TOTAL NUMBER OF LOTS: 61  
PROPOSED DENSITY: 3.39 D.U. PER ACRE  
DENSITY CALCULATION: (# OF LOTS/GROSS ACRES - 61/18.02=3.39)  
TYPICAL LOT SIZE: 55'x100'  
BUILDING HEIGHT: 2 STORIES AND 30'  
LOT SALES: YES  
COMMON RETENTION  
PARCEL(S): 301-20-001, 301-20-007C, 301-20-010G, 301-20-010J, 301-20-049B, 301-20-050, 301-23-003C AND 301-23-003F  
WATER, SEWER, AND SANITATION SERVICES BY THE CITY OF PHOENIX. ELECTRIC SERVICE BY S.R.P.  
GAS SERVICE BY SOUTHWEST GAS CORPORATION.  
TELEPHONE SERVICE BY CENTURYLINK  
CONSTRUCTION WITHIN PUBLIC UTILITY EASEMENT SHALL BE LIMITED TO UTILITIES, AND WOOD, WIRE OR REMOVABLE SECTION TYPE FENCING.  
ALL UTILITIES AND SINGLE PHASE ELECTRIC LINES ARE TO BE INSTALLED UNDERGROUND.  
40" MAXIMUM HEIGHT FOR TRANSFORMERS, CABINETS, AND OTHER EQUIPMENT WITHIN PERIMETER STREET FRONTAGES.

**LOT COVERAGE**

CALCULATION:  

$$\frac{\text{MAX. COVERAGE (\%)} \times \left( \frac{\text{NET AREA} - \text{STREET AREA}}{\text{# OF LOTS (PLUS 1 FOR OPEN SPACE)}} \right)}{62} = \text{MAX. ALLOWABLE AREA UNDER ROOF PER LOT}$$

$$\frac{(0.40) \left( \frac{17,6784 - 2,8731}{2,8731} \right) (43,560)}{62} = 4,161 \text{ S.F. MAXIMUM ALLOWABLE AREA PER LOT (ENCLOSED STRUCTURES)}$$

$$\frac{(0.10) \left( \frac{17,6784 - 2,8731}{2,8731} \right) (43,560)}{62} = 1,040 \text{ S.F. MAXIMUM ALLOWABLE AREA PER LOT (SHADE STRUCTURES)}$$



**OPEN SPACE**

GROSS ACRES: 18.0190 AC. OR 784,906 S.F. x .05 = 39,245 S.F. REQUIRED (MINIMUM 5% OF GROSS AREA REQUIRED) \* 207,861 S.F. PROVIDED \* (EXCLUDES AREA WITHIN LANDSCAPE SETBACK)


Revised

Date  
04-12-24  
As-Built  
Job No.  
230703


KIVA #23-1343  
SDEV #2300334  
Q.S. 01-36  
PAPP #2306597




TYPICAL PRIVATE ACCESSWAY  
LOOKING NORTH & WEST



S. 36TH WAY  
LOOKING NORTH



S. 36TH STREET  
SITE FRONTAGE (LOOKING NORTHEAST)



**CITY OF PHOENIX**  
MAY 31 2024  
Planning & Development  
Department

KIVA #23-1343  
SDEV #2300334  
Q.S. 01-36  
PAPP #2306597

**Clouse Engineering, Inc.**  
ENGINEERS - SURVEYORS  
5010 E. Shea Blvd Suite 110 Scottsdale, AZ 85254  
Tel 602-395-9300 Fax 602-395-9310

**PRELIMINARY SITE PLAN**  
**PRESERVE AT THE HIGHLINE**  
AN R1-6 PLANNED RESIDENTIAL DEVELOPMENT  
PHOENIX ARIZONA

Revised  
Date 04-12-24  
As-Built  
Job No. 230703  
2 OF 2

# THE PRESERVE AT THE HIGHLINE

## PHOENIX, ARIZONA

5/30/2024




CITY OF PHOENIX


MAY 31 2024

Planning & Development  
Department







FLOOR PLAN



FRONT ELEVATION



REAR ELEVATION



LEFT ELEVATION

RIGHT ELEVATION

# THE PRESERVE AT THE HIGHLINE


PORCHLIGHT HOMES  
PHO-1-24--Z-104-23-8

COPYRIGHT © 2024 - WARNING AND NOTICE OF RIGHTS - THIS WORK IS PROTECTED UNDER U.S. COPYRIGHT LAW. These plans may not be copied, in whole or in part, nor otherwise reproduced, changed or relied upon to create derivative or further works without the express, prior written permission. Infringements of works shall be prosecuted to the full extent of the law.

Proposed Conceptual Elevations

PLAN 1  
1,901 S.F.  
ELEVATION A - SANTA BARBARA CONTEMPORARY


LINDEROTH ASSOCIATES, INC.  
Hearing Date: July 17, 2024




FLOOR PLAN



FRONT ELEVATION



REAR ELEVATION



LEFT ELEVATION

RIGHT ELEVATION


# THE PRESERVE AT THE HIGHLINE

PORCHLIGHT HOMES  
PHO-1-24--Z-104-23-8


COPYRIGHT © 2024 - WARNING AND NOTICE OF RIGHTS - THIS WORK IS PROTECTED UNDER U.S. COPYRIGHT LAW. These plans may not be copied, in whole or in part, nor otherwise reproduced, changed or relied upon to create derivative or further works without the express, prior written permission. Infringements of works shall be prosecuted to the full extent of the law.

Proposed Conceptual Elevations


PLAN 1  
1,901 S.F.  
ELEVATION B - DESERT PRAIRIE  
LINDEROTH ASSOCIATES, INC.  
Hearing Date: July 17, 2024




FLOOR PLAN



FRONT ELEVATION



REAR ELEVATION



LEFT ELEVATION

RIGHT ELEVATION

# THE PRESERVE AT THE HIGHLINE




PORCHLIGHT HOMES  
PHO-1-24--Z-104-23-8

COPYRIGHT © 2024 - WARNING AND NOTICE OF RIGHTS - THIS WORK IS PROTECTED UNDER U.S. COPYRIGHT LAW. These plans may not be copied, in whole or in part, nor otherwise reproduced, changed or relied upon to create derivative or further works without the express, prior written permission. Infringements of works shall be prosecuted to the full extent of the law.

Proposed Conceptual Elevations





PLAN 1  
1,901 S.F.  
ELEVATION C - MID-CENTURY MODERN

LINDEROTH ASSOCIATES, INC.  
Hearing Date: July 17, 2024







# THE PRESERVE AT THE HIGHLINE







# THE PRESERVE AT THE HIGHLINE




# THE PRESERVE AT THE HIGHLINE




UPPER FLOOR PLAN




FRONT ELEVATION



FLOOR PLAN




REAR ELEVATION



LEFT ELEVATION

RIGHT ELEVATION

# THE PRESERVE AT THE HIGHLINE



UPPER FLOOR PLAN




FLOOR PLAN

WOOD FASCIA  
ACCENT W/ SAND FINISH STUCCO  
DECORATIVE STONE VENEER



CONCRETE ROOF TILE  
SAND FINISH STUCCO  
SECTIONAL GARAGE DOOR W/ WINDOWS  
DECORATIVE COACH LIGHT


FRONT ELEVATION



REAR ELEVATION

CONCRETE ROOF TILE  
WOOD FASCIA  
SAND FINISH STUCCO  
ACCENT W/ SAND FINISH STUCCO

26'-1" T.O. RIDGE  
9'-0" PL.  
F.F.  
10'-0" PL.  
F.F.



LEFT ELEVATION

RIGHT ELEVATION

CONCRETE ROOF TILE  
WOOD FASCIA  
SAND FINISH STUCCO  
DECORATIVE STONE VENEER

# THE PRESERVE AT THE HIGHLINE



UPPER FLOOR PLAN



FLOOR PLAN

DECORATIVE STONE VENEER  
 ACCENT W/ SAND FINISH STUCCO  
 SAND FINISH STUCCO




CONCRETE ROOF TILE  
 DECORATIVE COACH LIGHT  
 SECTIONAL GARAGE DOOR  
 W/ WINDOWS

FRONT ELEVATION



CONCRETE ROOF TILE  
 WOOD FASCIA  
 SAND FINISH STUCCO

REAR ELEVATION



CONCRETE ROOF TILE  
 DECORATIVE STONE VENEER  
 SAND FINISH STUCCO

LEFT ELEVATION

RIGHT ELEVATION

# THE PRESERVE AT THE HIGHLINE

Santa Barbara Contemporary			
	Scheme A-1	Scheme A-2	Scheme A-3
Roof Tile: Eagle Roofing Capistrano			
	8403 Santa Barbara Blend	8403 Santa Barbara Blend	8403 Santa Barbara Blend
Stucco Body			
	SW 7636 Origami White	SW 7035 Aesthetic White	SW 6378 Crisp Linen
Popout/ Recesses/ Fascia/ Trim			
	SW 7675 Sealskin	SW 7018 Dovetail	SW 7069 Iron Ore
Garage Door			
	SW 7675 Sealskin	SW 7018 Dovetail	SW 7069 Iron Ore
Entry Door			
	SW 6472 Composed	SW 6230 Rainstorm	SW 6327 Bold Brick

Desert Prairie			
	Scheme B-1	Scheme B-2	Scheme B-3
Roof Tile: Eagle Roofing Bel Air			
	SCB 8828 Bridgeport Blend	SCB 8828 Bridgeport Blend	SCB 8828 Bridgeport Blend
Stucco Body			
	SW 7632 Modern Gray	SW 7015 Repose Gray	SW 9173 Shitake
Popout/ Recesses/ Fascia/ Trim			
	SW 7048 Urbane Bronze	SW 7069 Iron Ore	SW 9175 Deep Forest Brown
Garage Door/ Entry Door & Shutters			
	SW 7040 Smokehouse	SW 7019 Gauntlet Gray	SW 7509 Tiki Hut
Masonry (Creative Mines)			
	Craft Split Modular Sea Pearl	Craft Split Modular Sea Pearl	Craft Split Modular Sea Pearl

Mid-Century Modern			
	Scheme C-1	Scheme C-2	Scheme C-3
Roof Tile: Eagle Roofing Bel Air			
	4511 Flintridge Gray	4511 Flintridge Gray	4511 Flintridge Gray
Stucco Body			
	SW 7010 White Duck	SW 7043 Worldly Gray	SW 7051 Analytical Gray
Stucco Body Accent			
	SW 7060 Attitude Gray	SW 7642 Paverstone	SW 7053 Adaptive Shade
Popout/ Recesses/ Fascia/ Trim			
	SW 7645 Thunder Gray	SW 7675 Sealskin	SW 7055 Enduring Bronze
Garage Door			
	SW 7645 Thunder Gray	SW 7675 Sealskin	SW 7055 Enduring Bronze
Entry Door & Shutters			
	SW 0032 Needlepoint Navy	SW 2831 Classic Gold	SW 7710 Brandywine
Masonry (Coronado Stone)			
	3" Split Limestone White	3" Split Limestone White	3" Split Limestone White

**PROJECT NOTES**  
 \* TRIM: INCLUDES ANY WOOD FASCIA, TAILS, OR BRACES, OVERHANG, CORBELS. ALL HEADERS, SILLS, SURROUNDS & RECESSES AT ALL WINDOWS, DOORS AND GARAGES. ALSO INCLUDES POP-OUT CAPS ON STONE AND BRICK VENEER.  
 ALL WINDOWS TO BE WHITE  
 BRICK INSTALLATION: BRICK SHOULD BE INSTALLED WITH RELATIVELY TIGHT AND SLIGHTLY RECESSED JOINTS. ALLOW GROUT TO SET UP SLIGHTLY, THEN WIPED WITH A WET SPONGE TO EXPOSE THE SAND. BEING CAREFUL TO STAY IN GROUT LINE AND NOT OBSCURE THE BRICK FACES WITH GROUT.  
 STONE INSTALLATION: STONE TO BE SET TIGHT, JOINTS TO BE RECESSED, WITH GROUT ALLOWED TO SETUP SLIGHTLY THEN SPONGED TO REVEAL SAND.  
 O'HAGIN ROOF VENTS: PAINT TO MATCH DEEPER EDGE OF ROOF BLEND  
 SHAKE ROOF TILE SHOULD BE DETAILED WITHOUT THE USE OF GABLE-END PIECES.  
 COLORS ARE SHERWIN WILLIAMS, PER CLIENT'S DESIGNATION.

# THE PRESERVE AT THE HIGHLINE



**CITY OF PHOENIX**  
NOV 29 2023  
Planning & Development  
Department



**CITY OF PHOENIX**  
NOV 29 2023  
Planning & Development  
Department  
Hearing Date: July 17, 2024





**CITY OF PHOENIX**

NOV 29 2023

**Planning & Development  
Department**

Hearing Date: July 17, 2024



**CITY OF PHOENIX**

NOV 29 2023

Planning & Development  
Department

Hearing Date: July 17, 2024



**CITY OF PHOENIX**

NOV 29 2023

Planning & Development  
Department

Hearing Date: July 17, 2024



**CITY OF PHOENIX**  
NOV 29 2023  
Planning & Development  
Department  
Hearing Date: July 17, 2024

**REZONING CASES**

11. **Application #:** **Z-104-23-8**  
**From:** R1-6 BAOD (Approved R1-10 BAOD), S-1 BAOD (Approved R1-10 BAOD), and S-1 BAOD  
**To:** R1-6 BAOD  
**Acreage:** 18.52  
**Location:** Northeast corner of 36th Street and Beverly Road  
**Proposal:** Single-family residential  
**Applicant:** Adam Baugh, Withey Morris Baugh, PLC  
**Owner:** Miguel and Yvonne Montiel Family Trust; All Other Property, LLP; and DK Square Investments, LLC  
**Representative:** Adam Baugh, Withey Morris Baugh, PLC

Ms. Racelle Escolar stated that Item No. 11 is Z-104-23-8 a request to rezone 18.52 acres at northeast corner of 36th Street and Beverly Road from various residential districts to R1-6 (Single-Family Residence District) in the Baseline Area Overlay District to allow single-family residential.

The South Mountain Village Planning Committee recommended approval, per the staff recommendation, with modifications and additional stipulations by a 13 to 0 vote (with one abstention).

Staff has no concerns on the proposed modifications for Stipulation Nos. 8 and 12 and added Stipulation No. 33 which was renumbered to 32.

Staff does have concerns and proposed modifications for several of the stipulations. These have been addressed in a memo released yesterday, posted online, and received in the Commissioners' packets. She would not go through all the stipulations in detail. They are all outlined in the memo.

Staff recommends approval, per the staff memo dated March 6, 2024.

Chairman Gaynor called on the applicant and gave him two minutes to speak.

Mr. Adam Baugh stated that this case has received unanimous approval by the Village Planning Committee and staff. This is not a question of whether it is compatible. The property is R1-6 and there is land around the R1-6. The proposal is an infill subdivision. It is only 61 lots. It is made up of three different owners. It is less dense than what the General Plan is, and it is the very kind of thing you would expect to see in this area. He wanted to go over some quick stipulation changes. They are in support of the memo recommended by staff, as was amended. Trent Marchuk, the Village Planning Committee Chair sent an email tonight with some suggested changes. Mr. Baugh is supportive of those

suggested changes. He is most interested in the following stipulations. He stated that they could ignore Stipulation No. 27, as it was corrected in the memo tonight. Regarding Stipulation No. 31, it was added at the Village to perform a traffic impact study to analyze the flow of traffic along Baseline Road and 36th Street. The applicant is in total support of the necessity of doing that. One of his concerns is he suspects Baseline Road and the volume that is on there today already triggers the warrants. Being a small 61-lot subdivision but having to cover the expense of a full traffic signal is in his opinion an undue burden for such a small infill neighborhood. It will probably drive up the costs beyond what they are trying to accommodate for this area. He simply proposed a minor change that says, rather than be responsible for all, that they be responsible towards a proportionate share of the funding. The second stipulation change he hoped the Planning Commission would entertain, is No. 33. There is a request, not from staff, or the Staff Report, or the applicant or any neighbor, but at the Village, one of the Village members asked that they could add a pedestrian crossing over the canal. There is a suggestion that was added afterwards, stating that they also maintain it, not just install it. There are 10 pedestrian crossings between the applicant and going east. There are another five pedestrian crossings going west of the property. He does not think that any of those are maintained by anybody else but the City or SRP. So, they might be one of the only ones being asked to take on this burden. He reminded them that they are a small 61-home subdivision. He respectfully requested that they would not be obligated to maintain it after installation. They do not mind installing it, but it is a public benefit that they do not need. He thought that the City would do that. SRP does not grant the applicant the obligation to do that.

Chairman Gaynor asked Mr. Baugh if he was going to cover all the stipulations.

Mr. Baugh responded that he only needed to change two of the stipulations.

Chairman Gaynor asked Mr. Baugh to cover Stipulation No. 37.

Mr. Baugh stated that Stipulation No. 37 was already addressed in the Staff Report.

Chairman Gaynor asked if there were any questions for Mr. Baugh.

Commissioner Gorraiz asked for Mr. Baugh to talk a little more about the request for the pedestrian bridge and the number and proximity of the other pedestrian bridges already in the area.

Mr. Baugh displayed an exhibit showing the current bridge. It is about 240 feet from their property corner. At the Village, they requested he add another bridge, which he displayed to the left of the current bridge, at the end of the 36th Street cul-de-sac. Those two bridges are approximately 1,400 feet from each other (a quarter mile). He does not have an exhibit for the next one. There is another

bridge about 2,000 feet away, to the west. There are about three pedestrian bridge crossings within a half mile of this property. There are 14 in total, between Central Avenue and I-10.

Commissioner Gorraiz stated that in the past when the Commission talked about having pedestrian anything, it involves the federal government and SRP. He asked if this is something that can be put in a stipulation.

Ms. Escolar responded that this stipulation was added by the Village Planning Committee. Staff is not very supportive of it, but they are accommodating the Village request. As part of the stipulation, it does require approval by SRP. They would have to work with them to get that approved through them.

Commissioner Gorraiz stated that they have always made people increase the size of the roadway, but had they ever asked them to be responsible for the maintenance of that roadway, or of anything the Planning Commission requires them to do.

Ms. Escolar responded that she contacted SRP to ask about the maintenance and how it is typically handled. What they typically do is they do not maintain these pedestrian crossings. They will have a license agreement with the City to maintain it. With this scenario, if this were to be approved by SRP, the City would also eventually want the HOA to take over the maintenance. That is something that the City would have to work out with the developer.

Mr. Matthews read the memo which stated, a good faith effort to engage with SRP. It seems like an unenforceable stipulation, being that the developer could just ask SRP, and that would be a good faith effort. He asked, if the applicant wants to respond; and if he has any qualms with that stipulation just being stricken legally, as part of the recommendation. He asked if it would torpedo key support for the community.

Mr. Baugh stated that they are fine with it stricken. The only neighbor who spoke about it, spoke against it. He stated that the applicant wants to be accommodating, but it is not a desire that they voted. The limitation they have is trying to fulfil something that is not on their property and is outside of their control.

Chairman Gaynor thought it seems like a hardship. He asked Mr. Baugh to share again how far the other bridge would be.

Mr. Baugh responded that the right side, east of them is an existing bridge. The new one is on the other end of the site. There is another one about 2,000 feet away, further west.

Chairman Gaynor stated that he would support striking that. He asked to have the stipulations shown again.

Ms. Escolar pointed out Stipulation No. 37. Staff does have it struck out. She stated, “~~and walls~~” is struck out.

Chairman Gaynor stated that he is fine with, “PROPORTIONATE SHARE OF FUNDING.” He called on Mr. Trent Marchuk to come up and speak in favor.

Mr. Baugh stated that Mr. Marchuk left earlier, around 7:00 p.m., but he wanted Mr. Baugh to say that he put his comments in email to Ms. Escolar.

Ms. Escolar stated that Mr. Marchuk did send an email just after 5:00 p.m. today, asking for some additional updates to the stipulations. She passed around the stipulations to the Commission members and stated that staff does not have concerns with any of the requested updates, except the last one with the approval part in Stipulation No. 35, because it deviates from the standard Planning Hearing Officer (PHO) process.

Chairman Gaynor asked who sent this document. He would read it, however, he did not like receiving things at 5:00 p.m., on the day of the hearing.

Ms. Escolar stated that Mr. Marchuk asked that Stipulation No. 30, which has been updated as Stipulation No. 29, in the memo, “AND 50”, be added, in reference to the lot number. That would be lots 28 through 39, and 50. Staff has no concerns with that.

Mr. Baugh offered to explain for the Chairman.

Chairman Gaynor asked Ms. Escolar to continue reading.

Ms. Escolar stated that the next request was related to Stipulation No. 34, which has been updated to Stipulation No. 33. This is related to the pedestrian bridge. It adds, “The developer shall undertake reasonable efforts to work with SRP (Salt River Project) to FUND AND install...”, (adding the “fund and” part). Lastly, Stipulation No. 37, which has been updated to Stipulation No. 35 is asking for the planning hearing officer hearing process include review “AND APPROVAL” by the South Mountain Village.

Ms. Escolar stated that typically the standard stipulation for PHO just includes review by the Village, and not approval. It is really semantics because they are a recommending body.

Chairman Gaynor asked if Mr. Baugh was comfortable with these changes.

Mr. Baugh stated that he was okay.



Acting Vice-Chairman Boyd stated that he was not comfortable putting on new stipulations that came in at 5:00 p.m. on the day of the hearing that he has not had the chance to review. He is already on the verge of being a no, from his comfortability with the number of stipulations that are going on a small subdivision and residential areas. This is getting to be a bit ridiculous, the amount we are going through. He thought that the proponent may be better suited bringing these up to Council where they can very easily add them on if they are well-suited at that time.

Commissioner Matthews asked if the Chair was entertaining a motion at this time.

Chairman Gaynor asked him to proceed.

Commissioner Matthews made a MOTION to approve Z-104-23-8, per the staff memo dated March 6, 2024 with the corollary that Stipulation No. 33 in that staff memo be stricken entirely.

Acting Vice-Chairman Boyd asked about Stipulation No. 31.

Commissioner Hu asked to make a comment.

Commissioner Matthews apologized and stated that he would reword his motion.

**Commissioner Matthews made a MOTION to approve Z-104-23-8, per the staff memo dated March 6, 2024 with the noted revisions in Stipulation No. 31, regarding “ITS PROPORTIONATE SHARE OF”, with Stipulation No. 33 completely stricken, and with “and walls” stricken in Stipulation No. 37.**

**Commissioner Gorraiz SECONDED the motion.**

Ms. Escolar asked for confirmation. She asked Commissioner Matthews if he asked for the deletion of Stipulation No. 33 or just the update to strike out “and maintain”.

Commissioner Matthews stated, regarding Stipulation No.33, the motion was to strike the entirety of Stipulation No. 33.

Ms. Escolar asked, him to confirm his motion for Stipulation No. 37.

Commissioner Matthews responded, just striking the “~~and walls~~”.

Ms. Escolar stated that is already reflected in the memos. She stated the motion should be fine.

Commissioner Hu commented on Stipulation No. 33, on the memo. Although she agreed that this is not an enforceable stipulation or a challenging one, as a resident of South Mountain, often when they walk around the canal having this pedestrian bridge and having good faith of working with a developer and the community desire to create more walkability and access around a nice multi-use trail, is something very desirable. She hoped that the developer would, in good faith, continue to work with the neighborhood and provide amenities to this area.

Commissioner Matthew shared a quick comment to clarify his reasoning for striking Stipulation No. 33. Typically, they try to tie infrastructure improvements like this to the impact that the developer is having. He does not see that connection here necessitating, similar to the traffic light, that the developer would cause such pedestrian traffic to necessitate a bridge at this location.

There being no further discussion, Chairman Gaynor called for a vote and the MOTION Passed 8-0 (Busching absent).

Stipulations:

1. Tracts "C", "H", "I", and "G", as generally depicted on the site plan date stamped January 17, 2024, shall be reserved for open space, as modified by the following stipulations and approved by the Planning and Development Department.
2. The undisturbed hillside area (above 10% per the approved Slope Analysis) shall remain undisturbed and be dedicated with a preservation easement except for Lot 27 and development of private accessways as generally depicted on the site plan date stamped January 17, 2024, as approved by the Planning and Development Department.
3. The existing home on Lot 27 shall remain and any improvements to this lot shall be reviewed and approved through a Hillside/Grading and Drainage Plan by the Planning and Development Department.
4. A physical feature (such as retaining wall, rock wall, etc.) shall be provided along the west and south portions of Tract "J", as generally depicted on the site plan date stamped January 17, 2024, to protect the undisturbed hillside area, as approved by the Planning and Development Department.
5. A minimum of three distinct exterior accent materials for each required standard plan within the subdivision shall be provided, as approved by the Planning and Development Department.
6. If fencing is proposed along the perimeter of the site, the fencing shall be a minimum of 75% view fencing, except on Lots 1, 50, 51, 52, and 53 as depicted on the site plan date stamped January 17, 2024, as approved by the Planning

and Development Department. Any perimeter fencing requirement adjacent to the Highline Canal is subject to review and approval of SRP.

7. All landscape setbacks shall be planted with minimum 2-inch caliper large canopy drought-tolerant trees, 20 feet on center or in equivalent groupings, with five 5-gallon shrubs per tree, as approved by the Planning and Development Department.
8. A minimum of 10% of the required shrubs, shall be a milkweed or other native nectar species, and shall be planted in groups of three or more AND MAINTAINED, as approved by the Planning and Development Department.
9. The sidewalk along 36th Street shall be a minimum of five feet in width and detached with a minimum five-foot wide landscape strip located between the sidewalk and back of curb and planted to the following standards, as approved by the Planning and Development Department.
  - a. Minimum 2-inch caliper, single-trunk, large canopy, drought-tolerant shade trees planted 20 feet on center or in equivalent groupings.
  - b. Drought tolerant vegetation to achieve a minimum of 75 percent live coverage at maturity.

Where utility conflicts exist, the developer shall work with the Planning and Development Department on alternative design solutions consistent with a pedestrian environment for installing the required plants.

10. Prior to preliminary plat approval, documentation shall be provided that demonstrates participation in the Environmental Protection Agency's WaterSense certification program, or an equivalent program, as approved by the Planning and Development and Water Services departments.
11. A WaterSense inspection report from a third-party verifier shall be submitted that demonstrates successful participation in the Environmental Protection Agency's WaterSense certification program, or an equivalent program, prior to certificate of occupancy, as approved by the Planning and Development Department.
12. IN ADDITION TO THE ~~Only~~ landscape materials listed in the Baseline Area Master Plan Plant List CERCIDIUM HYBRID (DESERT MUSEUM PALO VERDE), QUERCUS VIRGINIANA (LIVE OAK), AND PISTACIA X 'RED-PUSH (RED PUSH PISTACHE), MAY BE PERMITTED AS APPROVED BY PLANNING AND DEVELOPMENT DEPARTMENT AND shall be utilized throughout the subdivision including the front, side, and rear yards of individual residential lots. This restriction shall be included in the Covenants, Conditions, and Restrictions for the subdivision.

13. Landscaping in common areas shall be maintained by permanent and automatic/water efficient WaterSense labeled irrigation controllers (Smart Controller) to minimize maintenance and irrigation water consumption for all on and offsite landscape irrigation.
14. Pressure regulating sprinkler heads and drip lines shall be utilized in any turf areas to reduce water waste.
15. Natural turf shall only be utilized on individual single-family lots (behind the front yard); required retention areas (bottom of basin), and functional turf areas within common areas, as approved by the Planning and Development Department.
16. A minimum of two green infrastructure (GI) techniques for stormwater management shall be implemented per the Greater Phoenix Metro Green Infrastructure and Low-Impact Development Details for Alternative Stormwater Management, as approved or modified by the Planning and Development Department.
17. Swimming pools on individual single-family lots shall be limited to 600 square feet in size.
18. A public connection to the existing 36th Way stub street shall be provided or the existing 36th Way right-of-way shall be terminated per the City of Phoenix termination standards, as required by the Street Transportation Department.
19. An enhanced connection shall be provided on the southern site boundary to allow for direct pedestrian access to the adjacent Highline Canal. The developer shall construct an 8-foot-wide shaded pedestrian pathway consisting of decorative material such as brick, pavers or alternative material providing at the entryway, as approved by the Planning and Development Department.
20. A sidewalk easement shall be dedicated over a clearly defined pedestrian pathway(s) providing a public connection through the site from the existing 36th Way access point on the northern site boundary to the Highline Canal and the adjacent wash/trail system, as approved by the Planning and Development Department.
21. Replace unused driveways with sidewalk, curb, and gutter. Also, replace any broken or out-of-grade curb, gutter, sidewalk, curb ramps on all streets and upgrade all off-site improvements to be in compliance with current ADA guidelines.
22. All streets within and adjacent to the development shall be constructed with paving, curb, gutter, sidewalk, curb ramps, streetlights, median islands,

landscaping and other incidentals, as per plans approved by the Planning and Development Department. All improvements shall comply with all ADA accessibility standards.

23. The property owner shall record documents that disclose the existence, and operational characteristics of Phoenix Sky Harbor Airport to future owners or tenants of the property. The form and content of such documents shall be according to the templates and instructions provided which have been reviewed and approved by the City Attorney.
24. If determined necessary by the Phoenix Archaeology Office, the applicant shall conduct Phase I data testing and submit an archaeological survey report of the development area for review and approval by the City Archaeologist prior to clearing and grubbing, landscape salvage, and/or grading approval.
25. If Phase I data testing is required, and if, upon review of the results from the Phase I data testing, the City Archaeologist, in consultation with a qualified archaeologist, determines such data recovery excavations are necessary, the applicant shall conduct Phase II archaeological data recovery excavations.
26. In the event archaeological materials are encountered during construction, the developer shall immediately cease all ground-disturbing activities within a 33-foot radius of the discovery, notify the City Archaeologist, and allow time for the Archaeology Office to properly assess the materials.
27. Prior to final site plan approval, the landowner shall execute a Proposition 207 waiver of claims form. The waiver shall be recorded with the Maricopa County Recorder's Office and delivered to the City to be included in the rezoning application file for record.
28. BENCH SEATING SHALL BE PROVIDED NEAR THE WESTERN PEDESTRIAN CONNECTION, LOCATED BETWEEN LOTS 39 AND 50, AS DEPICTED ON THE SITE PLAN DATE STAMPED JANUARY 17, 2024, AND AS APPROVED BY THE PLANNING AND DEVELOPMENT DEPARTMENT.
- ~~29. A SIDEWALK SHALL NOT BE REQUIRED ALONG OPEN SPACE TRACT D.~~
- ~~30~~ 29. AT LEAST 50% OF THE RESIDENTIAL HOMES ABUTTING THE CANAL (LOTS 28 THROUGH 39, AS DEPICTED ON THE SITE PLAN DATE STAMPED JANUARY 17, 2024) SHALL BE A MAXIMUM OF ONE STORY OR 15 FEET IN HEIGHT, AS APPROVED BY THE PLANNING AND DEVELOPMENT DEPARTMENT.
- ~~31~~ 30. THE APPLICANT DEVELOPER SHALL PROVIDE EVIDENCE OF UNDERTAKING REASONABLE EFFORTS TO WORK WITH THE ADJACENT HOMEOWNERS ASSOCIATION TO THE NORTH, TO CLOSE OFF THE

FORMER ACCESS DRIVE EAST OF THE GROVES AT BASELINE SUBDIVISION BY INSTALLING A SOLID 4-FOOT TALL BLOCK WALL WITH A 2-FOOT VIEW FENCE ATOP, AT THE NORTHEAST CORNER OF THE PROPERTY SITE AND AT THE DRIVEWAY ENTRANCE ALONG BASELINE ROAD, WITH A LOCKED ACCESS GATE ON THE SOUTH END FOR MAINTENANCE AS NEEDED.

- ~~32 THE APPLICANT SHALL SUBMIT A TRAFFIC IMPACT STUDY TO THE  
31. PHOENIX STREETS AND TRANSPORTATION DEPARTMENT TO  
DETERMINE THE SCOPE OFFSITE IMPROVEMENTS REQUIRED AT 36th  
STREET AND BASELINE ROAD.~~

A TRAFFIC IMPACT ANALYSIS (TIA) SHALL BE SUBMITTED TO THE CITY FOR THIS DEVELOPMENT. NO PRELIMINARY APPROVAL OF PLANS SHALL BE GRANTED UNTIL THE ANALYSIS IS REVIEWED AND APPROVED BY THE STREET TRANSPORTATION DEPARTMENT. THE TIA SHALL INCLUDE SIGNAL WARRANT ANALYSIS FOR 36TH STREET AND BASELINE ROAD. IF THE APPROVED TIA DETERMINES THAT A SIGNAL IS WARRANTED AND IS APPROVED BY THE STREET TRANSPORTATION DEPARTMENT FOR INSTALLATION, THE DEVELOPER SHALL BE RESPONSIBLE FOR **ITS PROPORTIONATE SHARE OF** THE FUNDING AND CONSTRUCTION OF ALL RECOMMENDATIONS OF THE ANALYSIS.

- ~~33 THE SUBDIVISION SHALL HAVE NO MORE THAN 61 LOTS.  
32.~~

- ~~34 **EITHER THE DEVELOPER SHALL UNDERTAKE REASONABLE EFFORTS  
33. TO WORK WITH SRP TO INSTALL AND MAINTAIN A PUBLIC  
PEDESTRIAN BRIDGE SHALL BE INSTALLED ACROSS THE HIGHLINE  
CANAL AT THE PUBLIC SIDEWALK NEAR 36TH STREET, SUBJECT TO  
APPROVAL BY SRP AND THE CITY OF PHOENIX, OR \$50,000 SHALL BE  
DEPOSITED WITH THE CITY OF PHOENIX TO SUPPORT THE CITY'S  
CANAL BANK GUIDELINES ENCOURAGING PUBLIC PEDESTRIAN  
BRIDGES ACROSS THE CANAL.**~~

- ~~35. ANY GRADING AND DRAINAGE PLAN SHALL CONSIDER THE IMPACT OF  
A POTENTIAL BREACH OF THE HIGHLINE CANAL.~~

- ~~36 OUTSIDE HOUSE LIGHT BRIGHTNESS SHALL NOT EXCEED 3,000  
34. LUMENS PER FIXTURE.~~

- ~~33. ON-SITE LIGHTING WITHIN OPEN SPACE AREAS SHALL BE  
ACCOMPLISHED WITH LOW LEVEL, UNIFORM LIGHTING FIXTURES  
DISPERSED THOROUGHOUT THE SITE WITH A LUMEN RATING OF 3,000  
OR LESS.~~

- ~~37.~~  
~~35.~~  
**34.** THE CONCEPTUAL ELEVATIONS FOR FUTURE DEVELOPMENT (NEW HOMES) SHALL BE REVIEWED AND APPROVED, WITH SPECIFIC REGARD TO THE SINGLE-FAMILY DESIGN REVIEW GUIDELINES, BY THE PLANNING HEARING OFFICER THROUGH THE PUBLIC HEARING PROCESS, INCLUDING REVIEW ~~AND APPROVAL~~ BY THE SOUTH MOUNTAIN VILLAGE PLANNING COMMITTEE, FOR STIPULATION MODIFICATION PRIOR TO PRELIMINARY SITE PLAN APPROVAL. THIS IS A LEGISLATIVE REVIEW FOR CONCEPTUAL PURPOSES ONLY. SPECIFIC DEVELOPMENT STANDARDS AND REQUIREMENTS WILL BE DETERMINED BY THE PLANNING HEARING OFFICER, THE PLANNING AND DEVELOPMENT DEPARTMENT, ~~AND THE GUIDELINES OF SINGLE-FAMILY DESIGN REVIEW.~~
- ~~38.~~  
~~36.~~  
**35.** ANY INVASIVE PLANTS SHALL NOT BE ALLOWED ~~BE REMOVED BY THE DEVELOPER AND ANY HOMEOWNERS ASSOCIATION.~~
- ~~39.~~  
~~37.~~  
**36.** NATIVE MATERIALS, OR SIMILAR MATERIALS, SHALL BE USED FOR ALL EXTERIOR PERIMETER WALL COLUMNS ~~AND WALLS~~, AS APPROVED BY THE PLANNING AND DEVELOPMENT DEPARTMENT.

\*\*\*

- 4) **Z-104-23-8**: Presentation, discussion, and possible recommendation regarding a request to rezone 18.52 acres located at the northeast corner of 36th Street and Beverly Road **from** R1-6 BAOD (Approved R1-10 BAOD) (Single-Family Residence District, Baseline Area Overlay District, Approved Single-Family Residence District, Baseline Area Overlay District), S-1 BAOD (Approved R1-10 BAOD) (Ranch or Farm Residence, Baseline Area Overlay District, Approved Single-Family Residence District, Baseline Area Overlay District), and S-1 BAOD (Ranch or Farm Residence, Baseline Area Overlay District) **to** R1-6 BAOD (Single-Family Residence District, Baseline Area Overlay District) to allow single-family residential.

*Committee Member Darlene Jackson joined the meeting during this item bringing quorum to 14 members.*

### STAFF PRESENTATION

**Samuel Rogers**, staff, presented the request, the location of the subject site, the surrounding context, the General Plan Land Use Map designation, the policy plans in the area, the site plan, proposed elevations, the staff recommendation, the staff findings, and concluded by presenting the proposed stipulations.

**Committee Member George Brooks** asked about the number of shrubs that would be required to be milkweed or other native nectar species and asked about maintenance. **Mr. Rogers** explained that a minimum of ten percent of the required shrubs would be required to be milkweed or other native nectar species and stated that the landscape ordinance requires that landscape plans be enforced. **Committee Member Greg Brownell** asked about the enforcement of the landscape ordinance. Mr. Rogers explained that the landscape ordinance enforcement is complaint driven. Committee Member Brooks explained that he disliked that enforcement of the landscape ordinance is complaint driven.

**Committee Member Lee Coleman** asked for clarification on what a WaterSense inspection entails. **Mr. Rogers** explained Stipulation No. 11. Committee Member Coleman stated that single-family residential homes do not require a Certificate of Occupancy. **Committee Member Tamala Daniels** explained that a Certificate of Occupancy is required for single-family homes.

**Committee Member Brownell** asked that Stipulation No. 8 be updated to require the maintenance of the required milkweed or other native nectar species shrubs. **Mr. Rogers** stated that when writing stipulations there should be a comfort level of compliance by preliminary approval.

**Committee Member Gene Holmerud** asked about people covering up view fencing. **Mr. Rogers** explained that several lots had been excluded from the view fencing requirement to avoid privacy concerns.



**Committee Member Viera** asked how the plan is related to Climate Action Plan and heat mitigation goals. **Mr. Rogers** explained the water consumption, shading, and pedestrian accessibility stipulations.

**Committee Member Brownell** asked if there could be stipulation regarding the elimination of invasive species.

#### APPLICANT PRESENTATION

**Adam Baugh**, representing the applicant with Withey Morris Baugh, PLC., presented the development team, the subject site, the General Plan Land Use Map designation, the surrounding zoning, the proposal, alignment with City of Phoenix policy plans and requirements, the project amenities, proposed elevations, neighborhood outreach, and project benefits.

#### QUESTIONS FROM THE COMMITTEE

**Committee Member Brownell** asked to stipulate that walls shall be made of the same materials as South Mountain. **Mr. Baugh** asked about the type of stone, explained that the development is proposing a block wall, and stated that the stone could be incorporated into the wall columns, monument signs, and retaining wall.

**Committee Member Brooks** asked about the maintenance and number of the required milkweed or other native nectar species shrubs. **Mr. Baugh** suggested updated language for Stipulation No. 8 to require maintenance of the shrubs. **Mr. Rogers** explained that a minimum of ten percent of the required shrubs would be required to be milkweed or other native nectar species and stated five shrubs are required per tree.

**Committee Member Kay Shepard** asked why the project is proposing R1-6 rather than R1-10. **Mr. Baugh** explained that the proposal is for R1-6 because the proposed lot sizes. **Chair Trent Marchuk** asked if the project would be different if it was R1-10 versus R1-6 and asked if the applicant would be willing to consider R1-10. **Mr. Baugh** explained that he would have to do an analysis before committing to changing to R1-10 and stated he is willing to do the analysis.

**Committee Member Holmerud** asked about a 1950s Lincoln Continental that was on the site. **Mr. Baugh** stated it had been removed.

**Committee Member Busching** stated that she would like to discuss the additional stipulations that had discussed with the applicant. **Mr. Baugh** summarized the additional stipulations.

**Committee Member Busching** stated that the development should be limited to 61 lots and explained the need for a public pedestrian bridge across the Highline Canal. **Mr. Baugh** stated that the canal is managed by SRP.

**Vice Chair Arthur Greathouse III** asked about the proposed square footage and price range of the homes. **Ryan Larsen**, with Porchlight Homes, described the proposed square footage of the homes and explained the homes cost between \$560,000 and the low \$600,000s. **Vice Chair Greathouse** asked about studies on the surrounding area. Mr. Larsen confirmed that a market analysis had been completed.

**Committee Member Brooks** asked where the flood water will go once it leaves the property. **Jeff Giles**, with Clouse Engineering, explained City of Phoenix requirements and explained the water flow. Committee Member Brooks asked how many cubic feet of water is a 100 year flood. **Mr. Giles** stated that it is somewhere in the range of 400 CFS. **Committee Member Brownell** stated that there had been issues on another development with flooding and asked if Baseline Road has the stormwater capacity to take on all the water if the Highline Canal overflows. Mr. Giles explained that preliminary grading and drainage had been done, but the full engineering of the site had not been completed. Committee Member Brownell asked if any water is planned to be retained on individual lots. Mr. Giles explained water is proposed to be retained in retention basins. **Chair Marchuk** asked about any proposed stipulations. Committee Member Brooks explained his main concerns regarding flooding. Chair Marchuk stated that the drainage plan could be required to focus on Baseline Road.

**Committee Member Fatima Muhammad Roque** asked about the grading and drainage of Lot 27. **Mr. Baugh** explained that Lot 27 would not be altered. **Mr. Giles** explained that water will flow from Lot 27 to the north.

**Committee Member T. Daniels** explained that homes had been built on 24th Street adjacent to Highline Canal needed a flood wall and asked if a flood wall was proposed. **Mr. Giles** explained that the need for a flood wall will be determined during the site planning process. **Committee Member Busching** suggested some potential language for a stipulation regarding the Grading and Drainage report.

**Chair Marchuk** asked about Stipulation No. 8. **Mr. Baugh** explained that 36th Way would be closed and the stipulation allows for flexibility in the placement of the gate. **Mr. Rogers** explained the requirements to terminate public streets

#### PUBLIC COMMENT

**Mark Wright** explained he lives adjacent to the development, stated he met with the applicant team, thanked the applicant team for working with the community, stated he is in favor of the project, stated he has lived in the area for 20 years, stated there had been problems with the vacant property, explained his concerns about the stipulation requiring a public bench, stated concerns over the enforcement of what time construction is allowed to occur, and explained that a light will be needed on Baseline Road.

**Russel Varone** stated that the closure of the driveway that had been historically used to access Lot 27 will be a problem and asked about pedestrian access at the 36th Way gate. **Mr. Baugh** stated there would be pedestrian access at the 36th Way gate. **Committee Member Busching** stated that the HOA of Mr. Varone's subdivision should give the accessway to the adjacent homeowners. **Committee Member Coleman** asked about easements over the accessway. Mr. Baugh explained that the HOA owns the land and there is an existing access easement.

**Robert Dotterer** explained that he had spoken to six of his neighbors, stated they are opposed to developments that will diminish their property values, and stated that if the development diminishes property values the homeowners should be compensated. **Committee Member Coleman** asked if the list of addresses Mr. Dotterer has supplied all opposed the development. Mr. Dotterer explained that the list contains the homeowners in his subdivision. **Committee Member Darlene Jackson** asked how much property values would be diminished. Mr. Dotterer explained the cost of his home versus homes on Baseline. **Committee Member Busching** stated that mountain views are not guaranteed and asked if the applicant how many homes would have their mountain views affected. **Mr. Baugh** explained how the development team had considered preserving views of the mountain. Mr. Dotterer stated that the home had not gone up in value since he purchased, but the home value had doubled since the original construction.

**Vice Chair Greathouse** asked if the property could appreciate in value due to the new development. **Committee Member T. Daniels** stated that Mr. Dotterer's opinion is flawed, echoed Committee Member Busching's statement that mountain views are not guaranteed, stated when homebuyers pay premiums, explained she can see the mountain from her property further north and with two-story homes in the subdivision, and stated that the home price would appreciate due to the new development.

**Mr. Dotterer** asked if any restrictions on height could be placed on the homes adjacent to the Grove subdivision. **Mr. Larsen** explained that he does not want to dictate what homes are built. **Chair Marchuk** stated that he would advocate for lower homes along the Grove subdivision if there was not a larger landscape buffer proposed adjacent to the Grove subdivision.

**Committee Member T. Daniels** asked about the proposed elevations. **Mr. Baugh** explained that there are three elevations for each proposed floor plan.

FLOOR/PUBLIC DISCUSSION CLOSED: MOTION, DISCUSSION, AND VOTE

**Committee Member Busching** summarized the stipulations that should be modified and added.

**Committee Member T. Daniels** stated concerns with applicants not presenting the proposed elevations when the proposals come in front of the committee. **Chair Marchuk**

stated that a previous case had been required to come back to committee for review of the elevations. **Mr. Rogers** provided some possible stipulation language.

**Chair Marchuk** asked about a possible stipulation regarding requiring the materials of South Mountain in the walls. **Mr. Brownell** explained that he would like the materials stipulation on the columns of the walls.

### **MOTION**

**Committee Member Marcia Busching** made a motion to recommend approval of Z-104-23-8 per the staff recommendation with modifications and additional stipulations.

**Committee Member Greg Brownell** seconded the motion.

### **VOTE**

**13-0-1**, motion to recommend approval of Z-104-23-8 per staff recommendation with modifications and additional stipulations passed with Committee Members Aldama, Brooks, Brownell, Busching, Coleman, F. Daniels, T. Daniels, Holmerud, Jackson, Muhammad, Shepard, Viera, and Greathouse in favor and Marchuk abstained.

*Stipulations listed for clarity:*

- 1. Tracts "C", "H", "I", and "G", as generally depicted on the site plan date stamped January 17, 2024, shall be reserved for open space, as modified by the following stipulations and approved by the Planning and Development Department.*
- 2. The undisturbed hillside area (above 10% per the approved Slope Analysis) shall remain undisturbed and be dedicated with a preservation easement except for Lot 27 and development of private accessways as generally depicted on the site plan date stamped January 17, 2024, as approved by the Planning and Development Department.*
- 3. The existing home on Lot 27 shall remain and any improvements to this lot shall be reviewed and approved through a Hillside/Grading and Drainage Plan by the Planning and Development Department.*
- 4. A physical feature (such as retaining wall, rock wall, etc.) shall be provided along the west and south portions of Tract "J", as generally depicted on the site plan date stamped January 17, 2024, to protect the undisturbed hillside area, as approved by the Planning and Development Department.*
- 5. A minimum of three distinct exterior accent materials for each required standard plan within the subdivision shall be provided, as approved by the Planning and Development Department.*
- 6. If fencing is proposed along the perimeter of the site, the fencing shall be a minimum of 75% view fencing, except on Lots 1, 50, 51, 52, and 53 as depicted on the site plan date stamped January 17, 2024, as approved by the Planning and Development Department.*

*Department. Any perimeter fencing requirement adjacent to the Highline Canal is subject to review and approval of SRP.*

7. *All landscape setbacks shall be planted with minimum 2-inch caliper large canopy drought-tolerant trees, 20 feet on center or in equivalent groupings, with five 5-gallon shrubs per tree, as approved by the Planning and Development Department.*
8. *A minimum of 10% of the required shrubs, shall be a milkweed or other native nectar species, and shall be planted in groups of three or more **AND MAINTAINED**, as approved by the Planning and Development Department.*
9. *The sidewalk along 36th Street shall be a minimum of five feet in width and detached with a minimum five-foot wide landscape strip located between the sidewalk and back of curb and planted to the following standards, as approved by the Planning and Development Department.*
  - a. *Minimum 2-inch caliper, single-trunk, large canopy, drought-tolerant shade trees planted 20 feet on center or in equivalent groupings.*
  - b. *Drought tolerant vegetation to achieve a minimum of 75 percent live coverage at maturity.*

*Where utility conflicts exist, the developer shall work with the Planning and Development Department on alternative design solutions consistent with a pedestrian environment for installing the required plants.*

10. *Prior to preliminary plat approval, documentation shall be provided that demonstrates participation in the Environmental Protection Agency's WaterSense certification program, or an equivalent program, as approved by the Planning and Development and Water Services departments.*
11. *A WaterSense inspection report from a third-party verifier shall be submitted that demonstrates successful participation in the Environmental Protection Agency's WaterSense certification program, or an equivalent program, prior to certificate of occupancy, as approved by the Planning and Development Department.*
12. ***IN ADDITION TO THE ~~Only~~ landscape materials listed in the Baseline Area Master Plan Plant List **CERCIDIUM HYBRID (DESERT MUSEUM PALO VERDE), QUERCUS VIRGINIANA (LIVE OAK), AND PISTACIA X 'RED-PUSH (RED PUSH PISTACHE), MAY BE PERMITTED AS APPROVED BY PLANNING AND DEVELOPMENT DEPARTMENT AND** shall be utilized throughout the subdivision including the front, side, and rear yards of individual residential lots. This restriction shall be included in the Covenants, Conditions, and Restrictions for the subdivision.***

13. *Landscaping in common areas shall be maintained by permanent and automatic/water efficient WaterSense labeled irrigation controllers (Smart Controller) to minimize maintenance and irrigation water consumption for all on and offsite landscape irrigation.*
14. *Pressure regulating sprinkler heads and drip lines shall be utilized in any turf areas to reduce water waste.*
15. *Natural turf shall only be utilized on individual single-family lots (behind the front yard); required retention areas (bottom of basin), and functional turf areas within common areas, as approved by the Planning and Development Department.*
16. *A minimum of two green infrastructure (GI) techniques for stormwater management shall be implemented per the Greater Phoenix Metro Green Infrastructure and Low-Impact Development Details for Alternative Stormwater Management, as approved or modified by the Planning and Development Department.*
17. *Swimming pools on individual single-family lots shall be limited to 600 square feet in size.*
18. *A public connection to the existing 36th Way stub street shall be provided or the existing 36th Way right-of-way shall be terminated per the City of Phoenix termination standards, as required by the Street Transportation Department.*
19. *An enhanced connection shall be provided on the southern site boundary to allow for direct pedestrian access to the adjacent Highline Canal. The developer shall construct an 8-foot-wide shaded pedestrian pathway consisting of decorative material such as brick, pavers or alternative material providing at the entryway, as approved by the Planning and Development Department.*
20. *A sidewalk easement shall be dedicated over a clearly defined pedestrian pathway(s) providing a public connection through the site from the existing 36th Way access point on the northern site boundary to the Highline Canal and the adjacent wash/trail system, as approved by the Planning and Development Department.*
21. *Replace unused driveways with sidewalk, curb, and gutter. Also, replace any broken or out-of-grade curb, gutter, sidewalk, curb ramps on all streets and upgrade all off-site improvements to be in compliance with current ADA guidelines.*
22. *All streets within and adjacent to the development shall be constructed with paving, curb, gutter, sidewalk, curb ramps, streetlights, median islands, landscaping and other incidentals, as per plans approved by the Planning and Development Department. All improvements shall comply with all ADA accessibility standards*

23. *The property owner shall record documents that disclose the existence, and operational characteristics of Phoenix Sky Harbor Airport to future owners or tenants of the property. The form and content of such documents shall be according to the templates and instructions provided which have been reviewed and approved by the City Attorney.*
24. *If determined necessary by the Phoenix Archaeology Office, the applicant shall conduct Phase I data testing and submit an archaeological survey report of the development area for review and approval by the City Archaeologist prior to clearing and grubbing, landscape salvage, and/or grading approval.*
25. *If Phase I data testing is required, and if, upon review of the results from the Phase I data testing, the City Archaeologist, in consultation with a qualified archaeologist, determines such data recovery excavations are necessary, the applicant shall conduct Phase II archaeological data recovery excavations.*
26. *In the event archaeological materials are encountered during construction, the developer shall immediately cease all ground-disturbing activities within a 33-foot radius of the discovery, notify the City Archaeologist, and allow time for the Archaeology Office to properly assess the materials.*
27. *Prior to final site plan approval, the landowner shall execute a Proposition 207 waiver of claims form. The waiver shall be recorded with the Maricopa County Recorder's Office and delivered to the City to be included in the rezoning application file for record.*
28. **BENCH SEATING SHALL BE PROVIDED NEAR THE WESTERN PEDESTRIAN CONNECTION, LOCATED BETWEEN LOTS 39 AND 50 ON THE SITE PLAN DATE STAMPED JANUARY 17, 2024.**
29. **A SIDEWALK SHALL NOT BE REQUIRED ALONG OPEN SPACE TRACT D**
30. **AT LEAST FIFTY PERCENT OF THE RESIDENTIAL HOMES ABUTTING THE CANAL SHALL BE A MAXIMUM OF ONE STORY OR FIFTEEN FEET IN HEIGHT.**
31. **THE APPLICANT SHALL CLOSE OFF THE FORMER ACCESS DRIVE EAST OF THE GROVES AT BASELINE SUBDIVISION BY INSTALLING A SOLID 4' TALL BLOCK WALL WITH A 2' VIEW FENCE ATOP, AT THE NORTHEAST CORNER OF THE PROPERTY AND AT THE DRIVEWAY ENTRANCE ALONG BASELINE ROAD, WITH A LOCKED ACCESS GATE ON THE SOUTH END FOR MAINTENANCE AS NEEDED.**
32. **THE APPLICANT SHALL SUBMIT A TRAFFIC IMPACT STUDY TO THE PHOENIX STREETS AND TRANSPORTATION DEPARTMENT TO DETERMINE**

**THE SCOPE OFFSITE IMPROVEMENTS REQUIRED AT 36th STREET AND BASELINE ROAD.**

33. **THE SUBDIVISION SHALL HAVE NO MORE THAN 61 LOTS**
  34. **EITHER A PUBLIC PEDESTRIAN BRIDGE SHALL BE INSTALLED ACROSS THE HIGHLINE CANAL AT THE PUBLIC SIDEWALK NEAR 36TH STREET, SUBJECT TO APPROVAL BY SRP, OR \$50,000 SHALL BE DEPOSITED WITH THE CITY OF PHOENIX TO SUPPORT THE CITY'S CANAL BANK GUIDELINES ENCOURAGING PUBLIC PEDESTRIAN BRIDGES ACROSS THE CANAL.**
  35. **ANY GRADING AND DRAINAGE PLAN SHALL CONSIDER THE IMPACT OF A POTENTIAL BREACH OF THE HIGHLINE CANAL.**
  36. **OUTSIDE HOUSE LIGHT BRIGHTNESS SHALL NOT EXCEED 3,000 LUMENS PER FIXTURE.**
  37. **THE CONCEPTUAL ELEVATIONS FOR FUTURE DEVELOPMENT SHALL BE REVIEWED AND APPROVED BY THE PLANNING HEARING OFFICER THROUGH THE PUBLIC HEARING PROCESS, INCLUDING REVIEW AND APPROVAL BY THE SOUTH MOUNTAIN VILLAGE PLANNING COMMITTEE, FOR STIPULATION MODIFICATION PRIOR TO PRELIMINARY SITE PLAN APPROVAL. THIS IS A LEGISLATIVE REVIEW FOR CONCEPTUAL PURPOSES ONLY. SPECIFIC DEVELOPMENT STANDARDS AND REQUIREMENTS WILL BE DETERMINED BY THE PLANNING HEARING OFFICER, THE PLANNING AND DEVELOPMENT DEPARTMENT, AND THE GUIDELINES OF SINGLE-FAMILY DESIGN REVIEW.**
  38. **ANY INVASIVE PLANTS SHALL BE REMOVED BY THE DEVELOPER AND ANY HOMEOWNERS ASSOCIATION.**
  39. **NATIVE MATERIALS SHALL BE USED FOR ALL COLUMNS AND WALL.**
- 5) **INFORMATION ONLY**: Presentation and discussion regarding a proposed expansion of the Phoenix Central Business District boundaries.

**Xandon Keating**, with the Community and Economic Development, provided a presentation regarding the proposed expansion of the Phoenix Central Business District (CBD) boundaries. Mr. Keating provided the background of the CBD, how CBDs are used, the redevelopment Government Property Lease Excise Tax (GPLET) tool, an overview of Redevelopment Areas, the CBD expansion timeline, and the proposed CBD expansion area.

**Committee Member Greg Brownell** asked for confirmation that it is not possible to have a GPLET for one year. **Mr. Keating** confirmed Committee Member Brownell's statement regarding the GPLET duration.